

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FEDERAL 20% STATE ROADWAY
				0005 RURAL
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	38	38
40600990	TEMPORARY RAMP	SQ YD	416	416
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5940	5940
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	427	427
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	200	200
42400800	DETECTABLE WARNINGS	SQ FT	32	32
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	73300	73300
44000600	SIDEWALK REMOVAL	SQ FT	200	200
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	304	304
44201299	DOWEL BARS 1 1/2"	EACH	760	760
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	905	905
44213200	SAW CUTS	FOOT	1824	1824
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	24482	24482
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1436	1436

14

FILE NAME : c:\p\work\p\dot\ducaenbd\dm84470\0346042-ah-500.dgn	USER NAME : ducaenbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 553	SECTION 125 RS-4	COUNTY DEKALB	TOTAL SHEETS 26	SHEET NO. 4
	PLOT SCALE : 100.0000 1/16"	DRAWN -	REVISED -		SCALE:	SHEET NO. 2 OF 4 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				
	PLOT DATE : 3/20/2014	CHECKED -	REVISED -										
		DATE -	REVISED -										
CONTRACT NO. 66842													