

URBAN
100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0005 NONE	0014 SN 032-0075
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	1	1	0
40600527	LEVELING BINDER (HAND METHOD), IL-9.5FG, N50	TON	2	2	0
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50	TON	215	215	0
40600990	TEMPORARY RAMP	SO YD	48	32	16
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	534	417	117
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SO YD	1193	0	1193
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	4961	4961	0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	67	67	0
67100100	MOBILIZATION	L SUM	1	1	0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	356	356	0
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	94	94	0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7272	7272	0
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	424	424	0

FILE NAME *	USER NAME * #USER#	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
#FILE#		DRAWN - _____	REVISED - _____		SCALE: _____	SHEET _____	OF _____	SHEETS	STA. _____	TO STA. _____	297	(G-VBRS-1) & (FIRS-4)	GRUNDY	15	3
	PLOT SCALE * #SCALE#	CHECKED - _____	REVISED - _____		CONTRACT NO. 66080										
#MODELNAME#	PLOT DATE * #DATE#	DATE - _____	REVISED - _____		ILLINOIS FED. AID PROJECT										