

IL 71 MAINLINE SCHEDULE

			PVMT WIDTH	PVMT AREA	PVMT MARKING REMOVAL	RRPM REMOVAL	HIGH FRICTION SURFACE TREATMENT	SHORT-TERM PAVEMENT MARKING	WORK ZONE PVMT MARK. REMOVAL	RRPM	URETHANE PAVT MARK. 4" WHITE	URETHANE PAVT MARK. 4" YELLOW	MIX FOR CRACKS, JTS FLGWYS	AGGREGATE SHOULDER, TYPE B
	LENGTH	FOOT	SO YD	SO FT	EACH	SO YD	FOOT	SO FT	EACH	FOOT	FOOT	TON	TON	
START PROJECT	372+92.0 (127' W OF 950TH RD) TO 382+13.8	921.8	32	3277.5	1229	12	3278	92	31	12	1844	1844	1.0	70
STA EQUATION	382+13.8 BK = 382+02.0 AH													
	382+02.0 TO 384+10.0	208.0	32	739.6	277	3	740	21	7	3	416	416	0.2	16
	384+10.0 TO 388+96.0	486.0	30	1620.0	648	6	1620	49	16	6	972	972	0.5	
	388+96.0 TO 404+88.0	1592.0	30	5306.7	2123	20	5307	159	53	20	3184	3184	1.6	60
	404+88.0 TO 409+43.0	455.0	28	1415.6	607	6	1416	46	15	6	910	910	0.4	
	409+43.0 TO 427+25.0	1782.0	24	4752.0	2376	22	4752	178	59	22	3564	3564	1.4	
OMISSION	427+25.0 TO 450+00.0													
	450+00.0 TO 454+25.0	425.0	24	1133.3	567	5	1133	43	14	5	850	850	0.3	32
	454+25.0 TO 459+80.0	555.0	24	1480.0	740	7	1480	56	19	7	1110	1110	0.4	
	459+80.0 TO 467+58.0	1278.0	34	4828.0	1704	16	4828	128	43	16	2556	2556	1.4	
	467+58.0 TO 472+50.0	492.0	24	1312.0	656	6	1312	49	16	6	984	984		
	472+50.0 TO 490+47.0	1797.0	24	4792.0	2396	22	4792	180	60	22	3594	3594	1.4	136
	490+47.0 TO 505+50.0	1503.0	20	3340.0	2004	19	3340	150	50	19	3006	3006	1.0	
OMISSION	505+50.0 TO 531+20.0													
END PROJECT	531+20.0 TO 535+30.0 (555' E OF PARK ENTR.)	410.0	24	1093.3	547	5	1093	41	14	5	820	820	0.3	31
GRAND TOTAL					15873	150	35090	1190	397	150	23810	23810	10.1	345