



**NOTES:**

1. USE 6" D BLACK LETTERING ON FLOURESENT ORANGE BACKGROUND.
2. ERECT SIGNS AT LOCATIONS IN ADVANCE OF THE "ROAD CONSTRUCTION AHEAD" SIGNS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② A MINIMUM OF ONE WEEK PRIOR TO THE START OF THE LANE CLOSURE.
4. REMOVE PANEL ② ON THAT DATE.
5. SEE SPECIAL PROVISION "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. WILL BE PAID FOR PER SQ FT AS "TEMPORARY INFORMATION SIGNING". EACH SIGN = 21 SQ FT AND THE DATE PANEL ② WILL NOT BE MEASURED SEPARATELY FOR PAYMENT.

\* FAP 573 (US 30) & FAP 587 (US 34)  
 \*\* SECTION (19,20)RS-5&I-1 / (16)RS-4&I-1  
 \*\*\* DEKALB & LASALLE

FILE NAME =	USER NAME = fergusonse	DESIGNED - _____	REVISED - _____	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>DETAILS</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pw\work\p\idot\fergusonse\d0337253\0xxxxx-sht-cover.dgn	PLOT SCALE = 100.0000' / 1in.	DRAWN - _____	REVISED - _____			*	*	***	6	6	
\$MODELNAME\$	PLOT DATE = 3/28/2014	CHECKED - _____	REVISED - _____			CONTRACT NO. 66DB5					
		DATE - _____	REVISED - _____			ILLINOIS FED. AID PROJECT					