

GENERAL NOTES

PLAN DIMENSIONS RELATIVE TO THE EXISTING ROADWAY HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO MAKE NECESSARY ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

ALL EXCAVATED MATERIAL, WHICH INCLUDES DIGGING OR GRADING OF ANY SOIL OR FILL MATERIAL, WITH THE EXCEPTION OF AGGREGATE FILLS, MUST BE LEFT ON, OR INCORPORATED WITHIN, THE IDOT RIGHT OF WAY DUE TO ENVIRONMENTAL DOCUMENTATION REQUIREMENTS.

EXCAVATED MATERIALS SHALL BE DISPOSED OF AT LOCATIONS DIRECTED BY THE ENGINEER. ANY SUCH DISPOSAL SHALL NOT CREATE AND UNSIGHTLY OR OBJECTIONABLE APPEARANCE OR DETRACT FROM THE NATURAL TOPOGRAPHIC FEATURES WITHOUT WRITTEN PERMISSION FROM THE ENGINEER.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

GRANULAR MATERIALS	2.05	TONS / CU YD
MIX FOR CRACKS, JTS, & FLGWYS	0.0003	TONS / SQ YD
SHORT-TERM PAVEMENT MARKING	4	FT / 40 FT OF APPLICATION

US 30 US 34

CODE NO.	ITEM	UNIT	TOTAL	CONSTR. CODE	
				DEKALB	LASALLE
				FED / STATE 90% / 10%	FED / STATE 90% / 10%
				ROADWAY 0021 RURAL	ROADWAY 0021 RURAL
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5.2	2.2	3.0
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	650	272	378
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	182	91	91
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	81	34	47
78300100	PAVEMENT MARKING REMOVAL	SQ FT	8666	3628	5038
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	81	34	47
X0327693	HIGH FRICTION SURFACE TREATMENT	SQ YD	17346	7270	10076
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	25997	10884	15113
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	42	21	21

*Specialty Item

DATE: 3-28-14

PREPARED BY: Don Benoit
DISTRICT STUDIES & PLANS ENGINEER

EXAMINED BY: Harold Jany (unclear)
DISTRICT CONSTRUCTION ENGINEER

[Signature]
DISTRICT MATERIALS ENGINEER

[Signature]
DISTRICT OPERATIONS ENGINEER

FAP 573 (US 30) & FAP 587 (US 34)
SECTION (19.20RS-581-1 / 116RS-481-1)
DEKALB & LASALLE

FILE NAME: c:\pwork\pmdot\ferguson\0337253\0337253.dgn	USER NAME: ferguson	DESIGNED: DBS	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES AND SUMMARY OF QUANTITIES	SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.	F.A.I. RATE: *	SECTION: **	COUNTY: ***	TOTAL SHEETS: 6	SHEET NO.: 2	
PLOT SCALE: 100.0000 / in.	CHECKED: -	REVISED: -										
PLOT DATE: 3/28/2014	DATE: FEBRUARY 2013	REVISED: -										
CONTRACT NO. 66085 ILLINOIS FED. AID PROJECT												