

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | | | |
|------------|---|-------|----------------|-------------------|---------|------------|------------|
| | | | | LASALLE | LASALLE | LIVINGSTON | LIVINGSTON |
| | | | | ROADWAY | ROADWAY | ROADWAY | ROADWAY |
| | | | | 0005 | 0005 | 0005 | 0005 |
| | | | | RURAL | URBAN | RURAL | URBAN |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS | TON | 4.7 | 1.0 | 0.9 | 2.0 | 0.8 |
| 40600525 | LEVELING BINDER (HAND METHOD), N50 | TON | 7.7 | 1.7 | 1.5 | 3.2 | 1.3 |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 1734 | 378 | 342 | 723 | 291 |
| 44000157 | HOT-MIX ASPHALT SURFACE REMOVAL, 2" | SO YD | 15475 | 3371 | 3051 | 6453 | 2600 |
| 67100100 | MOBILIZATION | L SUM | 1.00 | 0.25 | 0.25 | 0.25 | 0.25 |
| 70100310 | TRAFFIC CONTROL AND PROTECTION, STANDARD T01421 | L SUM | 1.0 | 0.5 | 0.5 | 0.0 | 0.0 |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD T01306 | L SUM | 1.0 | 0.0 | 0.0 | 0.5 | 0.5 |
| 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 878 | 176 | 164 | 358 | 180 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SO FT | 293 | 59 | 55 | 119 | 60 |
| * 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 21782 | 1056 | 576 | 12950 | 7200 |
| * 78001130 | PAINT PAVEMENT MARKING - LINE 6" | FOOT | 8688 | 3000 | 3000 | 1788 | 900 |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 220 | 75 | 75 | 48 | 22 |
| X4060110 | BITUMINOUS MATERIALS (PRIME COAT) | POUND | 6964 | 1517 | 1373 | 2904 | 1170 |

100%
STATE

13

*Specialty Items

*INTERMITTENT SPRING ROAD REPAIR 2014-3
**LASALLE & LIVINGSTON

| | | | | | | | | | | | | |
|--|------------------------|------------|-----------|---|---------------------------|-------------------------|------|----------------|---------|--------|--------------|-----------|
| FILE NAME = | USER NAME = budzynskim | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| c:\pwwork\p1dot\budzynskim\40388885\066088-akt-SDD.dgn | DRAWN - | REVISED - | REVISED - | | SCALE: | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA. | ** | ** | 10 | 3 |
| PLOT SCALE = 100.0000' / 1" | CHECKED - | REVISED - | REVISED - | | CONTRACT NO. 66088 | | | | | | | |
| PLOT DATE = 4/11/2014 | DATE - | REVISED - | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | | | |