

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 0005 URBAN	ROADWAY 0005 RURAL
				40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS
40600535	LEVELING BINDER (HAND METHOD), N70	TON	25	9	16
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5686	2072	3614
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	800	400	400
42400800	DETECTABLE WARNINGS	SQ FT	160	80	80
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	50176	18503	32273
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	128	64	64
44000600	SIDEWALK REMOVAL	SQ FT	800	400	400
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	128	64	64
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	

• SPECIALTY ITEMS

FILE NAME = c:\pwwork\p1s\dot\carpentardj\d8587081\2-drawings\ht-500.dgn USER NAME = carpentardj PLOT SCALE = 100.0000 1/1 in. PLOT DATE = 4/11/2014				DESIGNED - DRAWN - CHECKED - DATE -				REVISED - REVISED - REVISED - REVISED -				STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.P. RTE. VAR		SECTION		COUNTY KANKAKEE		TOTAL SHEETS 24		SHEET NO. 3		CONTRACT NO. 66D91		ILLINOIS FED. AID PROJECT	
SCALE:		SHEET NO.		OF		SHEETS		STA.		TO STA.																							

• INTERMITTENT SPRING ROAD REPAIR 2014-6