

LOCATION	DESCRIPTION	LENGTH FT	PAINT PAVEMENT MARKING			MODIFIED URETHANE					RRPM REMOVAL EACH	RRPM WHITE EACH	RRPM AMBER EACH	PRISMATIC CURB REFLECTORS EACH	SHORT TERM PVT MK FT	WORK ZONE PVT MK REMOVAL SO FT	
			4"	4"	6"	4"	6"	8"	12"	24"							LETTERS & SYMBOLS SO FT
			YELLOW	WHITE	YELLOW	YELLOW	YELLOW	WHITE	WHITE	WHITE							
IL-9/IL-47																	
LM 10.96 TO LM 10.97	SKIP DASH	53					26								5	2	
LM 10.97 TO LM 11.09	NO PASS ZONE LT	634				950.4									63	21	
LM 11.09 TO LM 11.12	RAILROAD OMISSION	158															
LM 11.12 TO LM 11.15	NO PASS ZONE RT	158				238							245		16	5	
LM 11.15 TO LM 11.20	BRIDGE OMISSION SN 027-0085	265					132										
LM 11.20 TO LM 11.26	NO PASS ZONE BOTH	316.8				1267			322	30	114		54		32	11	
IL-9/IL-47 SUB-TOTAL			0	0	0	2455	159	322	30	270	299	0	0	0	16	39	
IL 54																	
LM 0.00 TO LM 0.12		602				4408		440	200	52	267	45	5	40	2197	245	
IL 54 SUB-TOTAL			0	0	0	4408	0	440	200	52	267	45	5	40	2197	245	
US 24																	
LM 0.00 TO LM 1.37	PASSING	7234		28934	3617							181			723	241	
LM 1.37 TO LM 1.39	BRIDGE OMISSION SN 027-0079	106			53												
LM 1.39 TO LM 2.22	PASSING	4382		600	2191							110			438	146	
LM 2.22 TO LM 2.35	NO PASS ZONE RT	686	1030	200								17			69	23	
LM 2.45 TO LM 2.68	NO PASS ZONE LT	1214	1822	4858								30			121	40	
LM 2.68 TO LM 3.45		4066		16262	2033							102			407	136	
LM 3.45 TO LM 3.48	BRIDGE OMISSION SN 027-0080	158			79												
LM 3.48 TO LM 4.06		3062		500	1531							77			306	102	
LM 4.06 TO LM 4.09	BRIDGE OMISSION SN 027-0081	158			79												
LM 4.09 TO LM 6.00		10085		1200	5042							252			1008	336	
US 24 SUB-TOTAL			2851.2	52554	14626	0	0	0	0	0	0	768	0	0	3073	1024	
IL 9																	
LM 10.10 TO LM 10.26	NO PASS ZONE RT	845	1267												84	28	
LM 10.26 TO LM 10.78	NO PASS ZONE BOTH	2746	10982												275	92	
LM 10.78 TO LM 10.82	BRIDGE OMISSION SN 027-0094	211			105.6												
LM 10.82 TO LM 10.95	SKIP DASH	686			343										69	23	
LM 10.95 TO LM 11.19	NO PASS ZONE LT/ EOP SOLID	1267	1901	2101											127	42	
LM 11.19 TO LM 12.52	SKIP DASH/ EOP SOLID	7022		3434	3511										702	234	
LM 12.52 TO LM 12.68	NO PASS ZONE RT	845	1267												84	28	
LM 12.68 TO LM 12.72	SKIP DASH	211			106										21	7	
LM 12.72 TO LM 12.87	NO PASS ZONE LT/ EOP SOLID	792	1188	1766											79	26	
LM 12.87 TO LM 13.02	SKIP DASH/ EOP SOLID	792		634	396										79	26	
LM 13.02 TO LM 13.13	NO PASS ZONE RT	581	871												58	19	
IL-9 SUB-TOTAL			17477	7934	4461.6	0	0	0	0	0	0	0	0	0	1579	526	
TOTAL			20328	60489	19087	6863	159	762	230	322	566	813	5	40	6965	1834	

* INTERMITTENT SPRING ROAD REPAIR 2014-7

FILE NAME =	USER NAME = mcfaddenka	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
e:\pwwork\pwwork\mcfaddenka\08387933\03xxxxx-sht-schedule.dgn	DRAWN -	REVISED -	VAR			.	FORD	11	7	
PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -	CONTRACT NO. 66092							
PLOT DATE = 4/11/2014	DATE -	REVISED -	SCALE:			SHEET OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		