

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE
				100% STATE
				0005
20800150	TRENCH BACKFILL	CU YD	33	33
21101615	TOPSOIL FURNISH & PLACE, 4"	SO YD	640	640
21400100	GRADING AND SHAPING DITCHES	FOOT	96	96
25000210	SEEDING, CLASS 2A	ACRE	0.3	0.3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	26	26
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	26	26
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	26	26
25100115	MULCH, METHOD 2	ACRE	0.3	0.3
28000500	INLET AND PIPE PROTECTION	EACH	2	2
30300106	AGGREGATE SUBGRADE IMPROVEMENT 6"	SO YD	418	418
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	27	27
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	23	23
40600990	TEMPORARY RAMP	SO YD	12	12
40603000	HOT - MIX ASPHALT BINDER COURSE, IL - 12.5, NSO	TON	139	139

FILE NAME =  
0468822-CADD.dgn

USER NAME = aubreyg

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 100.0000' / 1"

CHECKED -

REVISED -

PLOT DATE = 3/26/2014

DATE -

REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
626	43N	KNOX	34	7
CONTRACT NO. 68822				
ILLINOIS FED. AID PROJECT				