

TRENCH BACKFILL	
LOCATION	CU YD
2040+37.8 TO 2041+19 LT	7.8
2040+37.8 LT TO 2039+96 RT	24.9
TOTAL	33

GRADING AND SHAPING DITCHES	
LOCATION	FOOT
IL 97 STA. 2041+41.5 LT TO C.H. 20 STA. 8+71.5 LT	96
TOTAL	96

INLET AND PIPE PROTECTION	
LOCATION	EACH
2040+38 LT	1
2041+19	1
TOTAL	2

HMA SURFACE REMOVAL - BUTT JOINT	
LOCATION	SY
8+71.71 TO 8+81.71	23
TOTAL	23

CLASS D PATCHES, TYPE II, 12 INCH		
LOCATION	DIMENSIONS	AREA
	(FTXFT)	(SQ YD)
STA 2040+19 LT	9X14	14
TOTAL		14

CLASS D PATCHES, TYPE IV, 12 INCH		
LOCATION	DIMENSIONS	AREA
	(FTXFT)	(SQ YD)
STA 2040+19 RT	9X26	26
TOTAL		26

TEMPORARY RAMP			
LOCATION	LENGTH	WIDTH	AREA
	FT	FT	SY
8+71.71	20.5	5	11.5
TOTAL			12

PAVEMENT REMOVAL	
LOCATION	SQ YD
CO. Hwy 20 STA. 9+47.26 TO STA. 9+86	115.3
TOTAL	115

CONCRETE HEADWALL REMOVAL	
LOCATION	EACH
2040+31.50, 42' LT	1
2040+34, 48.5' LT	1
TOTAL	2

SEEDING AND FERTILIZER SUMMARY						
LOCATION	TOPSOIL FURNISH & PLACE	SEEDING, CLASS 2A	NITROGEN FERT. NUT.	PHOSPHORUS FERT. NUT.	POTASSIUM FERT. NUT.	MULCH, METHOD 2
STATION TO STATION	SQ YD	ACRES	LBS	LBS	LBS	ACRE
2038+46 TO 2040+02 RT	69.3	0.08	7.2	7.2	7.2	0.08
2038+83 TO 2040+51 LT	250.8	0.05	4.5	4.5	4.5	0.05
2040+95 TO 2041+69 LT	318.7	0.07	6.3	6.3	6.3	0.07
2042+48 TO 2044+50 LT		0.08	7.2	7.2	7.2	0.08
TOTAL	640	0.3	26	26	26	0.3

LOCATION	AGGREGATE SUBGRADE IMPROVEMENT 6"	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	HMA BINDER COURSE, IL-12.5, N50	HMA SURFACE COURSE, MIX "D", N50
STATION TO STATION	SQ YD	TON	TON	TON
CO. HIGHWAY 20 STA. 8+71.7 TO 9+85.8	418	0.3	139	43
TOTAL	418	0.3	139	43