MODIFIED URETHANE PAVEMENT MARKING - LINE 4"

78009004

	STATION	LENGTH	EDGE LINE	TURN LANE 4" LINE	SOLID	SKIP DASH	DOUBLE CENTERLINE	SHORT TERM PAVT MARKS (4)
			FOOT		FOOT			FOOT
			WHITE		YELLOW			(70300100)
								(PER App.)
								Foot
	FAP 741							
(1)	500+44.27							
		240.73	240.73		481.46	122.00		29.00
	502+85.00							
		1657.22			3,314.44	830.00		166.00
(2)	519+42.22							
		26.30					52.60	3.00
	519+68.52							
		82.77					165.54	9.00
	520+51.29			82.77				
	521+39.77							
		81.50					163.00	9.00
	522+21.27			81.50				
		263.15			526.30	132.00		27.00
	524+84.42							
	EQ.STA.							
	1079+79.84							
		716.15			1,432.30	359.00		72.00
	1072+63.69							
		363.69					727.38	37.00
	1069+00.00							
		75.35					150.70	8.00
	1068+24.65							
	1067+27.00							
		237.00					479.00	24.00
	1064+90.00							
	1064+25.27							
		189.51					384.02	19.00
	1062+35.76							
		2945.29				1,473.00		295.00
	1032+90.47							
		330.47			660.94			34.00
	1029+60.00							
		2078.67			4,157.34	1,040.00		208.00
	1008+81.33							
	1007+49.00							
		157.30			314.60			16.00
	1005+91.70			157.30				
		91.70			183.40			10.00
	1005+00.00							
		59.00			236.00			6.00
(1)	1004+41.00							
		294.80	589.60		1,179.20			89.00
	1001+46.20							
		1366.60	2,733.20			684.00		410.00
	987+79.60							
	18+15.09							
		1084.91	2,169.82			543.00		326.00
	29+00.00							
		130.00	260.00		260.00			39.00
	30+30.00							
		270.00	540.00		1,080.00			81.00
	33+00.00							
		93.00	93.00					28.00
	33+93.00							
		265.70	531.40		531.40			80.00
	36+58.70			265.70				
		244.30	488.60		488.60			74.00
	39+03.00							
		267.70	535.40		535.40			81.00
	41+70.70			267.70				
		110.30	110.30					34.00
	42+81.00							

MODIFIED URETHANE PAVEMENT MARKING - LINE 4" (CONT.)

78009004

STATION	LENGTH	EDGE LINE	TURN LANE 4" LINE	SOLID	SKIP DASH	DOUBLE CENTERLINE	SHORT TERM PAVT MARKS (4)
		FOOT		FOOT			FOOT
		WHITE		YELLOW			(70300100)
							(PER App.)
							Foot
42+54.51							
	20.04	40.08					7.00
42+74.55							
	25.45	50.90		101.80			8.00
43+00.00							
	71.86	143.72		143.72			22.00
43+71.86							
	128.14	256.28		256.28			39.00
45+00.00			128.14				
	377.77	755.54		755.54			114.00
48+77.77							
SUB-TOTAL		9,538.57	983.11	16,638.72	5,183.00	2,122.24	2,404.00
			34466				
FAU 7545							
60+88.50							
	65.90	131.80					20.00
61+54.40							
	838.86	1,677.72		1,677.72			252.00
69+93.26							
	106.74	213.48					33.00
71+00.00							
	140.43	280.86					43.00
72+40.43							
SUB-TOTAL		2,303.86		1,677.72			348.00
			3982				
SUBTOTAL	15498.30	11,842.43	983.11	18,316.44	5,183.00	2,122.24	5,504.00
TOTAL		12,825.54		25,621.68			5,504.00
USE			38,448.00				

(1) Per Article 703.04: l Aplication for Milling, 1 Application for Surface, Skip Dash and 2 Edge Lines
(2) 1 Application for Milling, 1 Application for Surface, Skip Dash only
(3) Concrete Median, no work on shoulder, no temporary markings required
(4) Work Zone Pavement Marks Removal is Surface Markings only, per single application rate shown above. Stop bars, railraod striping, islands and crosswalks should not be included in Short term Markings. Works Zone Pavement Marking Removal is computed in SQUARE FEET = FOOT/3

MODIFIED URETHANE PAVEMENT MARKING - LINE 6"

78009006

CROSSWALKS		FOOT
MONROE ST.	WEST	85
JEFFERSON ST	SOUTH	74
JEFFERSON ST	WEST	74.5
MARION ST	WEST	91
MARION ST	NORTH	94.5
LAFAYETTE ST.	EAST	108
MAIN ST.	EAST	86
WASHINGTON ST.	EAST	76
BRIDGE ST.	SOUTH	164
BRIDGE ST.	WEST	148
CENTER ST.	NORTH	151.5
CENTER ST.	EAST	85.5
WILSON ST.	NORTH	86
	SUBTOTAL	1324
ISLANDS		
E.1730 RD N:		179.9
42+27.82		314.25
	SUBTOTAL	494.15
	TOTAL	1818.2
	USE	1818.0