

SUMMARY OF QUANTITIES

LOCATION OF WORK:	LOCATION #1	LOCATION #2
	FAP 804 (PROSPECT AVE.)	FAP 811 (MATTIS AVE.)
	CHAMPAIGN COUNTY	CHAMPAIGN COUNTY
	VARIOUS	(STA. 48+71.00 TO STA. 13+99.00)
	URBAN	URBAN
FUNDING BREAKOUT:	100% STATE	100% STATE
CONSTRUCTION CODE:	0005	0005

PAY ITEM CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,507.0	1,180.0	1,327.0
40600300	AGGREGATE (PRIME COAT)	TON	51.0	24.0	27.0
40600990	TEMPORARY RAMP	SQ. YD.	628.0	432.0	196.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3,964.0	991.0	2,973.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ. YD.	11,794.0	11,794.0	-
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ. YD.	23,176.0	-	23,176.0
44201777	CLASS "D" PATCHES, TYPE II, 11 INCH	SQ. YD.	67.0	-	67.0
44201789	CLASS "D" PATCHES, TYPE II, 12 INCH	SQ. YD.	80.0	-	80.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	1.0	-	1.0
60255500	MANHOLES TO BE ADJUSTED	EACH	12.0	-	12.0
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70102625	TRAFFIC CONTROL AND PROTECTION 701606	L SUM	1.0	1.0	-
70102632	TRAFFIC CONTROL AND PROTECTION 701602	L SUM	1.0	0.5	0.5
70102635	TRAFFIC CONTROL AND PROTECTION 701701	L SUM	1.0	0.5	0.5