SUMMARY OF QUANTITIES

LOCATION OF WORK:	LOCATION #1	LOCATION #2
	FAP 804 (PROSPECT AVE.)	FAP 811 (MATTIS AVE.)
	CHAMPAIGN COUNTY	CHAMPAIGN COUNTY
	VARIOUS	(STA. 48+71.00 TO STA. 13+99.00)
	URBAN	URBAN
FUNDING BREAKOUT:	100% STATE	100% STATE
CONSTRUCTION CODE:	0005	0005

	PAY ITEM CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY	QUANTITY
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	333.0	44.0	289.0
*	88600100	DETECTOR LOOP, TYPE 1	FOOT	1,490.0	-	1,490.0
	X4406270	PARTIAL DEPTH REMOVAL, TYPE II, 7"	SQ. YD.	142.0	-	142.0
	X4406280	PARTIAL DEPTH REMOVAL, TYPE II, 8"	SQ. YD.	467.0	-	467.0
	X4406670	PARTIAL DEPTH REMOVAL, TYPE IV, 7"	SQ. YD.	67.0	-	67.0
	X4421000	PARTIAL DEPTH PATCHING	TON	277.0	-	277.0
*	X7830068	GROOVING FOR RECESSED PAVEMENT MARKING LETTERS AND SYMBOLS	SQ. FT.	3,052.0	-	3,052.0
*	X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	8,808.0	-	8,808.0
*	X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	537.0	-	537.0
*	X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	38.0	-	38.0
*	X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	393.0	-	393.0
	Z0010900	COLD MILLING (SPECIAL)	FOOT	10,409.0	6,055.0	4,354.0
	Z0048665	RR PROTECTIVE LIABLILITY INSURANCE	L SUM	1.0	-	1.0
	Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	1.0	-	1.0

* SPECIALTY ITEM