

# SCHEDULE OF QUANTITIES

70301000 WORK ZONE PAVEMENT MARKING REMOVAL							
LOCATION	STATION	TO	STATION	LENGTH (FOOT)	NO. OF APPLICATION (SURFACE ONLY)	(FOOT)	AREA (SQ FT)
NB	103+35.00		105+60.00	225.0	1	26.5	8.8
NB	106+50.00		112+00.00	550.0	1	59.0	19.6
SB	106+50.00		109+50.00	300.0	1	34.0	11.3
NB	115+00.00		116+80.00	180.0	1	22.0	7.3
SB	115+00.00		116+80.00	180.0	1	22.0	7.3
SB	116+80.00		134+30.00	1,750.0	1	179.0	59.6
NB	121+00.00		123+25.00	225.0	1	26.5	8.8
NB	124+05.00		126+00.00	195.0	1	23.5	7.8
NB	126+00.00		127+30.00	130.0	1	17.0	5.7
NB	128+80.00		131+00.00	220.0	1	26.0	8.7
NB	131+50.00		133+00.00	150.0	1	19.0	6.3
NB	133+00.00		134+50.00	150.0	1	19.0	6.3
NB	138+70.00		141+00.00	230.0	1	27.0	9.0
SB	140+50.00		143+70.00	320.0	1	36.0	12.0
SB	157+55.00		166+45.00	890.0	1	93.0	31.0
NB	157+70.00		161+30.00	360.0	1	40.0	13.3
NB	163+10.00		166+45.00	335.0	1	37.5	12.5
STOP BARS AT CHURCH ST.				24.0	1	72.0	24.0
TOTAL =							259.4
USE =							260.0

78009004 MODIFIED URETHANE PAVEMENT MARKING LINE 4"								78100100 RRPM AMBER (EACH)	78300200 RRPM REMOVAL (EACH)
LOCATION	STATION	TO	STATION	LENGTH (FOOT)	NO. OF APPLICATION	YELLOW (SKIP-DASH) (FOOT)	YELLOW SOLID (NO PASSING) (FOOT)		
NB	103+35.00		105+60.00	225.0	1.0	56.3	225.0	4.0	4.0
NB	106+50.00		112+00.00	550.0	1.0	137.5	550.0	8.0	8.0
SB	106+50.00		109+50.00	300.0	2.0	150.0	300.0	5.0	5.0
NB	115+00.00		116+80.00	180.0	1.0	45.0	180.0	4.0	4.0
SB	115+00.00		116+80.00	180.0	2.0	90.0	180.0	4.0	4.0
SB	116+80.00		134+30.00	1,750.0	1.0	437.5			
NB	121+00.00		123+25.00	225.0	1.0	56.3	225.0	4.0	4.0
NB	124+05.00		126+00.00	195.0	1.0	48.8	195.0	4.0	4.0
NB	126+00.00		127+30.00	130.0	1.0	32.5			
NB	128+80.00		131+00.00	220.0	1.0	55.0	220.0	4.0	4.0
NB	131+50.00		133+00.00	150.0	1.0	37.5			
NB	133+00.00		134+50.00	150.0	1.0	37.5	150.0	3.0	3.0
NB	138+70.00		141+00.00	230.0	1.0	57.5	230.0	4.0	4.0
SB	140+50.00		143+70.00	320.0	1.0	80.0			
SB	157+55.00		166+45.00	890.0	1.0	222.5			
NB	157+70.00		161+30.00	360.0	1.0	90.0			
NB	163+10.00		166+45.00	335.0	1.0	83.8			
SUB-TOTAL =						1,717.5	2,455.0	44.0	44.0
USE =						1,718.0	2,455.0	44.0	44.0
TOTAL YELLOW =						4173.00			
							TOTAL RRPM =	44.0	

NOTE: ITEM 70300220 - TEMPORARY PAVEMENT MARKING, LINE 4" QUANTITIES ARE EQUAL TO ITEM 78009004 QUANTITY.