

SCHEDULE OF QUANTITIES

70300220 - TEMPORARY PAVEMENT MARKING - LINE 4" (MAINLINE)

C/L - SKIP-DASH (WHITE)							70301000 WORK ZONE PVMNT MRK REM
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	(SQ FT)
FAP 811	48+71	-	36+18	S.B.	1	313.3	104.3
FAP 811	47+80	-	40+98	N.B.	1	170.5	56.8
FAP 811	40+08	-	36+18	N.B.	1	97.5	32.5
FAP 811	35+40	-	22+23	S.B.	1	329.3	109.6
FAP 811	35+40	-	29+74	N.B.	1	141.5	47.1
FAP 811	28+83	-	22+23	N.B.	1	165.0	54.9
FAP 811	21+00	-	19+52	N.B.	1	37.0	12.3
FAP 811	20+84	-	18+63	S.B.	1	55.3	18.4
FAP 811	18+63	-	11+45.74	N.B. & S.B.	2	358.6	119.4
FAP 811	11+75.86	-	12+34	N.B. & S.B.	2	29.1	9.7
FAP 811	13+54	-	13+99	N.B.	1	11.3	3.7
FAP 811 SUB-TOTAL =						1708.2	568.8

70300220 - TEMPORARY PAVEMENT MARKING - LINE 4" (MAINLINE)

TWO WAY LEFT TURN LANE - SOLID (YELLOW)							70301000 WORK ZONE PVMNT MRK REM
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	(SQ FT)
FAP 811	47+80	-	40+98	N.B. & S.B.	2	1364.0	454.2
FAP 811	40+08	-	37+16	N.B. & S.B.	2	584.0	194.5
FAP 811	35+40	-	29+74	N.B. & S.B.	2	1132.0	377.0
FAP 811	28+83	-	26+98.35	N.B. & S.B.	2	369.3	123.0
FAP 811	26+90.35	-	24+24	N.B. & S.B.	2	532.7	177.4
FAP 811	18+63	-	13+00	N.B. & S.B.	2	1126.0	375.0
FAP 811	13+00	-	12+89	S.B.	1	11.0	3.7
FAP 811 SUB-TOTAL =						5119.0	1704.6

TWO WAY LEFT TURN LANE - SKIP-DASH (YELLOW)

TWO WAY LEFT TURN LANE - SKIP-DASH (YELLOW)							70301000 WORK ZONE PVMNT MRK REM
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	(SQ FT)
FAP 811	47+80	-	40+98	N.B. & S.B.	2	341.0	113.6
FAP 811	40+08	-	37+16	N.B. & S.B.	2	146.0	48.6
FAP 811	35+40	-	29+74	N.B. & S.B.	2	283.0	94.2
FAP 811	28+83	-	26+98.35	N.B. & S.B.	2	92.3	30.7
FAP 811	26+90.35	-	24+24	N.B. & S.B.	2	133.2	44.3
FAP 811	18+63	-	13+00	N.B. & S.B.	2	281.5	93.7
FAP 811	13+00	-	12+89	S.B.	1	2.8	0.9
FAP 811 SUB-TOTAL =						1279.8	426.2

70300220 - TEMPORARY PAVEMENT MARKING - LINE 4" (MAINLINE)

SINGLE TURN LANE - SOLID (WHITE)							70301000 WORK ZONE PVMNT MRK REM
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	(SQ FT)
FAP 811	36+96	-	36+18	N.B.	1	78.0	26.0
FAP 811	23+29	-	22+23	N.B.	1	106.0	35.3
FAP 811	20+84	-	19+52	N.B.	1	132.0	44.0
FAP 811	12+13	-	11+45.74	N.B.	2	134.5	44.8
FAP 811	11+75.86	-	12+34	N.B.	2	116.3	38.7
FAP 811	13+54	-	13+99	S.B.	2	90.0	30.0
FAP 811 SUB-TOTAL =						656.8	218.7

SINGLE TURN LANE - DOUBLE SOLID (YELLOW)

SINGLE TURN LANE - DOUBLE SOLID (YELLOW)							70301000 WORK ZONE PVMNT MRK REM
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	(SQ FT)
FAP 811	37+16	-	36+18	N.B. & S.B.	1	196.0	65.3
FAP 811	24+24	-	22+23	N.B. & S.B.	1	402.0	133.9
FAP 811	20+84	-	19+52	N.B. & S.B.	1	264.0	87.9
FAP 811	12+89	-	11+45.74	N.B. & S.B.	2	573.0	190.8
FAP 811	11+75.86	-	12+34	N.B. & S.B.	2	232.6	77.4
FAP 811	13+54	-	13+99	N.B. & S.B.	1	90.0	30.0
FAP 811 SUB-TOTAL =						1757.6	585.3

FAP 811 TOTAL (4") = 10521.4
 FAP 811 USE (4") = 10522.0

* TOTAL WORK ZONE PAVEMENT MARKING REMOVAL COMES FROM ADDITIONAL PAY ITEMS.

70300240 - TEMPORARY PAVEMENT MARKING - LINE 6"

6" SOLID (WHITE)				70301000 WORK ZONE PVMNT MRK REM
ROUTE	LOCATION	DESCRIPTION	LENGTH (FOOT)	(SQ FT)
FAP 811	PARKLAND WAY	CROSSWALK	106.0	53.0
FAP 811	PAULA DR.	CROSSWALK	273.0	136.5
FAP 811	BLOOMINGTON RD.	CROSSWALK	158.0	79.0
FAP 811 SUB-TOTAL =			537.0	268.5

FAP 811 TOTAL (6") = 537.0

* TOTAL WORK ZONE PAVEMENT MARKING REMOVAL COMES FROM ADDITIONAL PAY ITEMS.

70300260 TEMPORARY PAVEMENT MARKING - LINE 12" (MAINLINE)

12" DIAGONAL (YELLOW)					70301000 WORK ZONE PVMNT MRK REM
ROUTE	STATION	TO	STATION	LENGTH (FOOT)	(SQ FT)
FAP 811	12+89	-	12+34	37.4	37.4
FAP 811 SUB-TOTAL =				37.4	37.4

FAP 811 TOTAL (12") = 37.4
 FAP 811 USE (12") = 38.0

* TOTAL WORK ZONE PAVEMENT MARKING REMOVAL COMES FROM ADDITIONAL PAY ITEMS.