

# SCHEDULE OF QUANTITIES

78100100 RRPM (MAINLINE)										78300200 RRPM REMOVAL (MAINLINE)				88600100 - DETECTOR LOOP, TYPE 1		
C/L - SKIP-DASH (WHITE)														ROUTE	LOCATION	LENGTH (FOOT)
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	ONE-WAY CRYSTAL RRPM (EACH)	ONE-WAY AMBER RRPM (EACH)	TWO-WAY AMBER RRPM (EACH)	RRPM REMOVAL (EACH)	FAP 811	FAP 811	FAP 811	FAP 811	FAP 811	FAP 811	
FAP 811	48+71	-	36+18	S.B.	1	16.0	-	-	16.0							
FAP 811	47+80	-	40+98	N.B.	1	9.0	-	-	9.0							
FAP 811	40+08	-	36+18	N.B.	1	5.0	-	-	5.0							
FAP 811	35+40	-	22+23	S.B.	1	17.0	-	-	17.0							
FAP 811	35+40	-	29+74	N.B.	1	8.0	-	-	8.0							
FAP 811	28+83	-	22+23	N.B.	1	9.0	-	-	9.0							
FAP 811	21+00	-	19+52	N.B.	1	2.0	-	-	2.0							
FAP 811	20+84	-	18+63	S.B.	1	3.0	-	-	3.0							
FAP 811	18+63	-	11+45.74	N.B. & S.B.	2	18.0	-	-	18.0							
FAP 811	11+75.86	-	12+34	N.B. & S.B.	2	2.0	-	-	2.0							
FAP 811	13+54	-	13+99	N.B.	1	1.0	-	-	1.0							
FAP 811 SUB-TOTAL						90.0	-	-	90.0							

FAP 811 TOTAL = 1490.0

TWO WAY LEFT TURN LANE - SOLID AND SKIP-DASH (YELLOW)									
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	ONE-WAY CRYSTAL RRPM (EACH)	ONE-WAY AMBER RRPM (EACH)	TWO-WAY AMBER RRPM (EACH)	RRPM REMOVAL (EACH)
FAP 811	47+80	-	40+98	N.B. & S.B.	2	-	-	35.0	35.0
FAP 811	40+08	-	37+16	N.B. & S.B.	2	-	-	15.0	15.0
FAP 811	35+40	-	29+74	N.B. & S.B.	2	-	-	29.0	29.0
FAP 811	28+83	-	26+98.38	N.B. & S.B.	2	-	-	10.0	10.0
FAP 811	26+90.38	-	24+24	N.B. & S.B.	2	-	-	14.0	14.0
FAP 811	18+63	-	13+00	N.B. & S.B.	2	-	-	29.0	29.0
FAP 811	13+00	-	12+89	S.B.	1	-	-	1.0	1.0
FAP 811 SUB-TOTAL						-	-	133.0	133.0

78100100 RRPM (MAINLINE)										78300200 RRPM REMOVAL (MAINLINE)			
SINGLE TURN LANE - SOLID (WHITE)													
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	ONE-WAY CRYSTAL RRPM (EACH)	ONE-WAY AMBER RRPM (EACH)	TWO-WAY AMBER RRPM (EACH)	RRPM REMOVAL (EACH)				
FAP 811	36+96	-	36+18	N.B.	1	2.0	-	-	2.0				
FAP 811	23+29	-	22+23	N.B.	1	3.0	-	-	3.0				
FAP 811	20+84	-	19+52	N.B.	1	4.0	-	-	4.0				
FAP 811	12+13	-	11+45.74	N.B.	2	4.0	-	-	4.0				
FAP 811	11+75.86	-	12+34	N.B.	2	3.0	-	-	3.0				
FAP 811	13+54	-	13+99	S.B.	2	3.0	-	-	3.0				
FAP 811 SUB-TOTAL						19.0	-	-	19.0				

78100100 RRPM (MAINLINE)										78300200 RRPM REMOVAL (MAINLINE)			
SINGLE TURN LANE - DOUBLE SOLID (YELLOW)													
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	ONE-WAY CRYSTAL RRPM (EACH)	ONE-WAY AMBER RRPM (EACH)	TWO-WAY AMBER RRPM (EACH)	RRPM REMOVAL (EACH)				
FAP 811	37+16	-	36+18	N.B. & S.B.	1	-	-	5.0	5.0				
FAP 811	24+24	-	22+23	N.B. & S.B.	1	-	-	11.0	11.0				
FAP 811	20+84	-	19+52	N.B. & S.B.	1	-	-	7.0	7.0				
FAP 811	12+89	-	11+45.74	N.B. & S.B.	2	-	15.0	-	15.0				
FAP 811	11+75.86	-	12+34	N.B. & S.B.	2	-	6.0	-	6.0				
FAP 811	13+54	-	13+99	N.B. & S.B.	1	-	-	3.0	3.0				
FAP 811 SUB-TOTAL						-	21.0	26.0	47.0				

FAP 811 TOTAL = 109.0 21.0 159.0 289.0