

INDEX OF SHEETS

1. COVER
2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS
3. SUMMARY OF QUANTITIES
4. PLAN
5. TYPICAL SECTIONS
6. SCHEDULES

HIGHWAY STANDARDS

- 701001-02 OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY FROM EDGE OF PAVEMENT
 701006-05 OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM EDGE OF PAVEMENT
 701011-04 OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
 701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
 701306-03 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATION DAY ONLY, FOR SPEEDS > 45 MPH
 701311-03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS DAY ONLY
 701901-03 TRAFFIC CONTROL DEVICES

GENERAL NOTES

1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.

| MIXTURE REQUIREMENTS | |
|--|----------------|
| THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT | |
| MIXTURE USE(S): | H.M.A. SURFACE |
| AC/PG: | PG 64-22 |
| DESIGN AIR VOIDS: | 4.0% @ N50 |
| MIXTURE COMPOSITION: | IL 9.5 |
| FRICTION AGGREGATE: | MIX C |
| QUALITY MANAGEMENT: | QC/QA |

| | |
|---|--|
| STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6 | |
| EXAMINED | March 21 20 14 <i>Michael P. [Signature]</i> for Regent Driskell ENGINEER OF OPERATIONS |
| EXAMINED | MARCH 4 20 14 <i>[Signature]</i> ENGINEER OF PROJECT IMPLEMENTATION |
| EXAMINED | March 6 20 14 <i>2RML-1</i> ENGINEER OF PROGRAM DEVELOPMENT |