

INDEX OF SHEETS

- 1. COVER
- 2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS
- 3. SUMMARY OF QUANTITIES
- 4. PLAN
- 5-7. TYPICAL SECTIONS
- 8. SCHEDULES

HIGHWAY STANDARDS

- 442201-03 CLASS C AND D PATCHES
- 701001-02 OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY FROM EDGE OF PAVEMENT
- 701006-05 OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM EDGE OF PAVEMENT
- 701011-04 OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
- 701201-04 LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS > 45 MPH
- 701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701306-03 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATION DAY ONLY, FOR SPEEDS > 45 MPH
- 701326-04 LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING > 45 MPH
- 701311-03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS DAY ONLY
- 701901-03 TRAFFIC CONTROL DEVICES

GENERAL NOTES

- 1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.

MIXTURE REQUIREMENTS		
THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT		
MIXTURE USE(S):	SURFACE	BASE COURSE WIDENING
AC/PG:	PG 64-22	PG 64-22
DESIGN AIR VOIDS:	4.0% @ N50	4.0% @ N50
MIXTURE COMPOSITION:	IL 9.5	IL 19.0
FRICITION AGGREGATE:	MIX C	N/A
QUALITY MANAGEMENT:	QC/QA	QC/QA

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED	March 31 20 14 <i>Mitchell P. Forrester, DMS/KSI</i> ENGINEER OF OPERATIONS
EXAMINED	MARCH 27 20 14 <i>Jimmy Lee</i> ENGINEER OF PROJECT IMPLEMENTATION
EXAMINED	March 18 20 14 <i>2RMLY</i> ENGINEER OF PROGRAM DEVELOPMENT