

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LOCATION #1	LOCATION #2
				CONSTR. CODE	CONSTR. CODE
				100% STATE	100% STATE
				ROADWAY 0005 S.N.	ROADWAY 0005 S.N.
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING 9"	SO YD	467	0	467
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.4	4.2	0.2
40600300	AGGREGATE (PRIME COAT)	TON	22.8	22.0	0.8
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.5	0.5
40600990	TEMPORARY RAMP	SO YD	32.7	32.7	0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50	TON	1,272.5	1,232	40.5
44000100	PAVEMENT REMOVAL	SO YD	323	0	323
44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	SO YD	10,992	10,992	0
44000400	GUTTER REMOVAL	FOOT	600	0	600
44201373	CLASS C PATCHES, TYPE I, 12 INCH	SO YD	250	250	0
44201377	CLASS C PATCHES, TYPE II, 12 INCH	SO YD	250	250	0

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LOCATION #1	LOCATION #2
				CONSTR. CODE	CONSTR. CODE
				100% STATE	100% STATE
				ROADWAY 0005 S.N.	ROADWAY 0005 S.N.
48101200	AGGREGATE SHOULDERS, TYPE B	TON	205	177	28
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	936	936	0
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	16,452	14,402	2,050
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	312	312	0
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	16,452	14,402	2,050
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	52	52	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	52	52	0

* SPECIALTY ITEM

10

11