

SHOULDER IMPROVEMENTS											
BITUMINOUS MATERIAL (PRIME COAT) RATE - 0.00038 T/SY AGGREGATE (PRIME COAT) RATE - 0.002 T/SY BITUMINOUS SURFACE / BINDER (112 LBS) RATE - 0.056 T/SY*IN							40600200 BITUMINOUS MATERIALS (PRIME COAT)	40600300 AGGREGATE (PRIME COAT)	40603320 HMA SURFACE COURSE MIX "X" N# d: 2"	44000157 HMA SURFACE REMOVAL, 2"	64200116 SHOULDER RUMBLE STRIPS, 16"
LOCATION (FAI 55, SB) STA TO STA - PL/DL		LENGTH FT	WIDTH FT	AREA SQ YD	TON	TON	TON	SQ YD	FOOT		
STA. 450+90.00	TO STA. 453+18.20 PL	228.20	4	101.42	0.04	0.20	11.36	101.42	228.20		
STA. 453+18.20	TO STA. 455+02.93 PL	184.73	4 TO 10	143.68	0.05	0.29	16.09	143.68	184.73		
STA. 455+02.93	TO STA. 456+67.37 PL	164.44	10	182.71	0.07	0.37	20.46	182.71	164.44		
STA. 447+00.00	TO STA. 456+67.37 DL	967.37	10	1074.86	0.41	2.15	120.38	1074.86	967.37		
STA. 467+89.89	TO STA. 469+89.87 PL	199.98	10	222.20	0.08	0.44	24.89	222.20	199.98		
STA. 469+89.87	TO STA. 471+02.64 PL	112.77	10 TO 4	87.71	0.03	0.18	9.82	87.71	112.77		
STA. 471+02.64	TO STA. 472+84.00 PL	181.36	4	80.60	0.03	0.16	9.03	80.60	181.36		
STA. 467+89.89	TO STA. 474+82.00 DL	692.11	10	769.01	0.29	1.54	86.13	769.01	692.11		
TOTAL:					1.01	5.32	298.17	2662.19	2730.96		
USE:					1.0	5.3	298	2662	2731		

70301000 WORK ZONE PAVEMENT MARKING REMOVAL, SQ FT (w = 4")				
LOCATION (FAI 55, SB) STA TO STA - SB/NB	LENGTH FT	APPLICA- TION	TOTAL LENGTH FT	AREA SQ FT
SN 084-0019				
STAGE I				
STA. 447+00.00 TO STA. 474+82.00 SB	2782	3	8346	2782.00
STAGE II				
STA. 405+20.00 TO STA. 433+00.00 SB	2780	3	8340	2780.00
STA. 433+00.00 TO STA. 472+84.00 SB	3984	2	7968	2656.00
SN 084-0014 TO 0017				
STAGE I				
STA. 577+00.00 TO STA. 613+68.00 SB	3668	1	3668	1222.67
STA. 590+88.00 TO STA. 639+50.00 NB	4862	1	4862	1620.67
STAGE II				
STA. 577+00.00 TO STA. 596+00.00 SB	1900	1	1900	633.33
STA. 596+00.00 TO STA. 598+82.00 RAMP	282	1	282	94.00
STA. 597+60.00 TO STA. 598+82.00 RAMP	122	1	122	40.67
STA. 597+60.00 TO STA. 612+25.00 SB	1465	1	1465	488.33
STA. 590+88.00 TO STA. 596+00.00 NB	512	1	512	170.67
STA. 596+00.00 TO STA. 600+00.00 RAMP	400	1	400	133.33
STA. 599+00.00 TO STA. 600+00.00 RAMP	100	1	100	33.33
STA. 599+00.00 TO STA. 605+90.00 NB	690	1	690	230.00
STA. 604+60.00 TO STA. 605+90.00 RAMP	130	1	130	43.33
STA. 605+40.00 TO STA. 607+50.00 RAMP	210	1	210	70.00
STA. 607+50.00 TO STA. 622+60.00 NB	1510	1	1510	503.33
STA. 620+25.00 TO STA. 622+60.00 RAMP	235	1	235	78.33
STA. 620+25.00 TO STA. 624+50.00 RAMP	425	1	425	141.67
STA. 624+50.00 TO STA. 639+50.00 NB	1500	1	1500	500.00
TOTAL:				14221.67
USE:				14222

** SHORT TERM PAVEMENT MARKING, FOOT			
LOCATION (FAI 55, SB) STA TO STA - SB/NB	LENGTH FT	APPLICA- TION	TOTAL LENGTH FT
SN 084-0019			
STAGE I			
STA. 447+00.00 TO STA. 474+82.00 SB	2782	3	8346
STAGE II			
STA. 405+20.00 TO STA. 433+00.00 SB	2780	3	8340
STA. 433+00.00 TO STA. 472+84.00 SB	3984	2	7968
SN 084-0014 TO 0017			
STAGE I			
STA. 577+00.00 TO STA. 613+68.00 SB	3668	1	3668
STA. 590+88.00 TO STA. 639+50.00 NB	4862	1	4862
STAGE II			
STA. 577+00.00 TO STA. 596+00.00 SB	1900	1	1900
STA. 596+00.00 TO STA. 598+82.00 RAMP	282	1	282
STA. 597+60.00 TO STA. 598+82.00 RAMP	122	1	122
STA. 597+60.00 TO STA. 612+25.00 SB	1465	1	1465
STA. 590+88.00 TO STA. 596+00.00 NB	512	1	512
STA. 596+00.00 TO STA. 600+00.00 RAMP	400	1	400
STA. 599+00.00 TO STA. 600+00.00 RAMP	100	1	100
STA. 599+00.00 TO STA. 605+90.00 NB	690	1	690
STA. 604+60.00 TO STA. 605+90.00 RAMP	130	1	130
STA. 605+40.00 TO STA. 607+50.00 RAMP	210	1	210
STA. 607+50.00 TO STA. 622+60.00 NB	1510	1	1510
STA. 620+25.00 TO STA. 622+60.00 RAMP	235	1	235
STA. 620+25.00 TO STA. 624+50.00 RAMP	425	1	425
STA. 624+50.00 TO STA. 639+50.00 NB	1500	1	1500
TOTAL:			42665
USE:			42665

\*\* THE COST OF INSTALLING TEMPORARY PAVEMENT MARKING SHALL BE INCLUDED IN THE TRAFFIC CONTROL AND PROTECTION PAY ITEM. IT WILL NOT BE PAID SEPARATELY.