



					PROPC	SED PRIVATE	ENTRANCE WORK				
LOCATION	ENTRANCE TYPE	MAILBOX	DRIVEWAY PAVEMENT REMOVAL	HMA ENTRANCE WIDTH "A" (PROPOSED)	HMA ENTRANCE WIDTH "B" (PROPOSED)	HMA ENTRANCE DEPTH "C" (PROPOSED)	AGG. SURF. CRSE. WIDTH "D" (PROPOSED)	HMA ENTRANCE AREA (PROPOSED)	PREPARATION OF BASE	HMA SHOULDERS. 6 1/2"	AGGREGATE SURF COURSE, TYPE (2" AVG. DEPTH
			44000200						35800100	48203023	40200800
			(SQ YD)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)
STA 659+00.00 LEFT		TURNOUT	38.9	62.8	20.0	5.0		23.7	23.7	23.7	
STA 659+36.00 RIGHT	AGG P.E.			46.0	38.0	4.0	24.0	18.7	42.8	18.7	2.7
STA 172+45.00 LEFT	AGG P.E.			46.0	38.0	4.0	24.0	18.7	42.8	18.7	2.7
STA 183+09.00 LEFT	BIT F.E.		47.3								
STA 202+91.00 LEFT	AGG P.E.			46.0	38.0	4.0	24.0	18.7	42.8	18.7	2.7
STA 206+82.00 LEFT	AGG P.E.		16.6	34.0	26.0	4.0	12.0	13.4	28.2	13.4	1.7
STA 238+00.00 LEFT	AGG P.E.		10.3	38.0	30.0	4.0	16.0	15.1	33.0	15.1	2.0
STA 243+92.00 LEFT	AGG P.E.			38.0	30.0	4.0	16.0	15.1	33.0	15.1	2.0
STA 275+97.00 RIGHT	AGG P.E.		42.7	42.0	34.0	4.0	20.0	16.9	37.9	16.9	2.4
STA 277+74.00 LEFT	AGG P.E.	TRAILING EDGE	52.6	66.6	44.0	5.0	16.0	30.7	48.6	30.7	2.0
STA 304+39.00 LEFT	AGG P.E.	LEADING EDGE	45.9	84.1	53.0	5.0	24.0	36.9	61.4	36.9	2.8
STA 361+05.00 RIGHT	AGG P.E.		19.4	34.0	26.0	4.0	12.0	13.4	28.2	13.4	1.7
STA 361+05.00 LEFT		TURNOUT	27.1	62.8	20.0	5.0		23.7	23.7	23.7	
STA 364+63.00 RIGHT	AGG P.E.		26.8	38.0	30.0	4.0	16.0	15.1	33.0	15.1	2.0
STA 402+00.00 LEFT	AGG P.E.		15.4	38.0	30.0	4.0	16.0	15.1	33.0	15.1	2.0
TOTALS =			343.0					275.2	512.1	275.2	26.7



PLAN VIEW - EARTH / AGGREGATE P.E.







PLAN VIEW - MAILBOX TURNOUT WITHOUT ENTRANCE

FILE NAME =	USER NAME = sparksgw	DESIGNED - RTS	REVISED -		SCHEDULES OF QUANTITIES			F.A.P.	SECTION	COUNTY TOTAL SHE
c:\pw_work\pwidot\sparksgw\d0219881\D672	693-sht-schedule.dgn	DRAWN - RTS	REVISED -	STATE OF ILLINOIS		SONEDULES OF GUARTITIES	-	315	(123) I-1	MASON 64 9
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION						CONTRACT NO. 72G9
Default	PLOT DATE = Apr-18-2014 02:00:30PM	DATE - 3-24-2014	REVISED -		SCALE:	SHEET 3 OF 5 SHEETS STA. TO	O STA.		ILLINOIS FED. AI) PROJECT

