

SUBBASE GRANULAR MATERIAL SCHEDULE				
LOCATION STATION TO STATION	LENGTH	WIDTH	SUBBASE GRANULAR MATERIAL TYPE B, 6" (SQ YD)	
FAP 745 (IL 104)				
LEFT				
STA. 1253+70.00 TO STA. 1256+60.00	290	5	161.1	
STA. 1262+70.00 TO STA. 1265+60.00	290	5	161.1	
STA. 1267+81.00 TO STA. 1269+74.00	193	5	107.2	
STA. 1271+77.00 TO STA. 1276+30.00	453	5	251.7	
RIGHT				
STA. 1253+70.00 TO STA. 1257+90.00	420	5	233.3	
STA. 1262+29.00 TO STA. 1265+60.00	331	5	183.9	
STA. 1267+61.00 TO STA. 1269+10.00	149	5	82.8	
STA. 1271+35.00 TO STA. 1276+30.00	495	5	275.0	
TOTAL			1456.1	

RAISED REFLECTIVE PAVEMENT MARKERS			
LOCATION STATION TO STATION	LENGTH (FT)	TWO-WAY AMBER (EACH)	REMOVAL (EACH)
FAP 745 (IL 104)			
STA. 1253+70.0 TO STA. 1276+30.0	2260.00	29	29
TOTAL		29	29

PCC BASE COURSE WIDENING SCHEDULE				
LOCATION STATION TO STATION	LENGTH	WIDTH	PCC BASE COURSE WIDENING, 10" (SQ YD)	STRIP REFLECTIVE CRACK CONTROL (FOOT)
FAP 745 (IL 104)				
LEFT				
STA. 1253+70.00 TO STA. 1256+60.00	290	2	64.4	290
STA. 1262+70.00 TO STA. 1265+60.00	290	2	64.4	290
STA. 1267+81.00 TO STA. 1269+74.00	193	2	42.9	193
STA. 1271+77.00 TO STA. 1276+30.00	453	2	100.7	453
RIGHT				
STA. 1253+70.00 TO STA. 1257+90.00	420	2	93.3	420
STA. 1262+29.00 TO STA. 1265+60.00	331	2	73.6	331
STA. 1267+61.00 TO STA. 1269+10.00	149	2	33.1	149
STA. 1271+35.00 TO STA. 1276+30.00	495	2	110.0	495
TOTAL			582.5	2621.0

SHORT-TERM PAVEMENT MARKING					
LOCATION STATION TO STATION	LENGTH (FT)	SPACING	NUMBER OF APPLICATIONS	SHORT-TERM PAVE MARK (FT)	WORK ZONE PAVE MARK REM (SQ FT)
FAP 745 (IL 104)					
STA. 1253+70.0 TO STA. 1276+30.0	2260.00	4' / 40'	3	690.0	226
TOTAL				690	226

PAVEMENT MARKING					
LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	SPACING	LINE-5"	
				YELLOW (FT)	WHITE (FT)
FAP 745 (IL 104)					
STA. 1253+70.00 TO STA. 1275+25.00	SKIP-DASH (CENTER)	2155.00	10' @ 40'	538.75	-
STA. 1264+34.00 TO STA. 1276+30.00	SOLID (EAST BOUND NPZ)	1196.00	-	1196.00	-
STA. 1275+25.00 TO STA. 1276+30.00	SOLID (WEST BOUND NPZ)	105.00	-	105	-
STA. 1253+70.00 TO STA. 1276+30.00	SOLID (EDGE LINE RT)	2260.00	-	-	2260.00
STA. 1253+70.00 TO STA. 1276+30.00	SOLID (EDGE LINE LT)	2260.00	-	-	2260.00
TOTAL				1839.75	4520.00