

TEMPORARY RAMPS			
LOCATION STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
FAP 550 (IL-99)			
MAINLINE			
401+50.00	7.5	24	20
409+00.00	7.5	24	20
TOTAL			40

SHORT-TERM PAVEMENT MARKING					
LOCATION STATION TO STATION	LENGTH (FT)	SPACING	NUMBER OF APPLICATIONS	SHORT-TERM PAVE MARK (FT)	WORK ZONE PAVE MARK REM (SQ FT)
FAP 550 (IL 99)					
STA. 401+50.00 TO STA. 409+00.00	750.00	4' / 40'	2	158.0	75
TOTAL				158	75

GUARDRAIL SCHEDULE			
LOCATION STATION TO STATION	VERTICAL ADJUSTMENT OF GUARDRAIL (FOOT)	VERT. ADJ. TRAF. BAR. TERM. TYPE 1 SPL (TANGENT) (EACH)	
FAP 550 (IL-99)			
RIGHT			
STA. 402+35.00 TO STA. 408+35.00	600	2	
TOTAL		600	2

PAVEMENT MARKING					
LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	SPACING	LINE-5"	
				YELLOW (FT)	WHITE (FT)
FAP 550 (IL 99)					
STA. 401+50.00 TO STA. 409+00.00	SOLID (NORTH BOUND NPZ)	750.00	-	750.00	-
STA. 401+50.00 TO STA. 409+00.00	SOLID (SOUTH BOUND NPZ)	750.00	-	750.00	-
STA. 401+50.00 TO STA. 409+00.00	SOLID (EDGE LINE RT)	750.00	-	-	750.00
STA. 401+50.00 TO STA. 409+00.00	SOLID (EDGE LINE LT)	750.00	-	-	750.00
TOTAL				1500	1500

RAISED REFLECTIVE PAVEMENT MARKERS			
LOCATION STATION TO STATION	LENGTH (FT)	TWO-WAY AMBER (EACH)	REMOVAL (EACH)
FAP 550 (IL 99)			
STA. 401+50.00 TO STA. 409+00.00	750.00	10	10
TOTAL		10	10

PAVEMENT SCHEDULE							
LOCATION STATION TO STATION	LENGTH	WIDTH	HMA SURF. REM. BUTT-JOINT (SQ YD)	HMA SURF. REM. (2") (SQ YD)	HMA SURF. COURSE MIX "C" N50 (2") (TON)	BIT. MAT. PRIME CT. (TON)	AGG. PRIME CT. (TON)
FAP 550 (IL 99)							
STA. 401+50.00 TO STA. 401+57.50	7.50	24	20.00	-	1.68	0.01	0.04
STA. 401+57.50 TO STA. 408+92.50	735.00	24	-	1960.00	164.64	0.74	3.92
STA. 408+92.50 TO STA. 409+00.00	7.50	24	20.00	-	1.68	0.01	0.04
TOTAL			40.0	1960.0	168.0	0.8	4.0

RIPRAP SCHEDULE					
LOCATION STATION	LENGTH (FT)	WIDTH (FT)	RIPRAP CLASS 3 (SQ YD)	EARTH EX (SPECIAL) (CU YD)	FRENCH DRAIN (CU YD)
FAP 550 (IL-99)					
MAINLINE					
STA. 432+00.00 TO STA. 433+00.00	100	20	222.22	185.20	
STA. 432+00.00 TO STA. 433+50.00	150	1			16.60
TOTAL			222.22	185.20	16.60

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -
ct:\pw\work\p\dot\sparksgw\0387531\0672\01-sht-schedule.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = Apr-18-2014 09:49:41AM	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
IL-99 BROWN COUNTY			
SCALE:	SHEET	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	*	12	8
CONTRACT NO.			72H01	
ILLINOIS FED. AID PROJECT				