



PAY ITEM	UNIT	QUADRANT
		SW
SIDEWALK REMOVAL	SQ FT	93.0
CURB REMOVAL	FT	23.0
COMB. CONC. CURB & GUTTER REMOVAL	FT	18.0
COMB. CONC. CURB & GUTTER, TYPE B-6.24	FT	18.0
PCC SIDEWALK 4"	SQ FT	93.0
DETECTABLE WARNINGS	SQ FT	10.0

- NOTES:
1. SEE STANDARD 424011 FOR ADDITIONAL INFORMATION.
 2. REMOVAL LIMITS ARE TO EXISTING JOINTS.
 3. THE COST OF SIDE CURB SHALL BE INCLUDED IN PCC SIDEWALK 4".

→ DRAINAGE FLOW ARROW

LANDING AREA - 4' X 4' MIN. 5' X 5' TYPICAL
MAX 2.0% , 1.56% IS PREFERRED SLOPE IN ALL DIRECTIONS

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
c:\pwork\pwork\stevfenmk\d0187107\074475-shit-sidewalk-details.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 15.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/4/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SIDEWALK DETAILS
LAKESHORE DR.**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
712	128RS-4,148KRS-2	Macon	73	41
ILLINOIS FED. AID PROJECT			CONTRACT NO. 74475	