


PAY ITEM	UNIT	QUADRANT	
		SW	NW
SIDEWALK REMOVAL	SQ FT	183.0	134.0
COMB. CONC. CURB & GUTTER REMOVAL	FT	41.0	28.0
COMB. CONC. CURB & GUTTER, TYPE B-6.12	FT	41.0	
COMB. CONC. CURB & GUTTER, TYPE B-6.24	FT		28.0
PCC SIDEWALK 4"	SQ FT	183.0	134.0
DETECTABLE WARNINGS	SQ FT	10.0	10.0
HANDHOLE TO BE ADJUSTED	EA	1.0	1.0

- NOTES:
1. SEE STANDARD 424011 FOR ADDITIONAL INFORMATION.
 2. REMOVAL LIMITS ARE TO EXISTING JOINTS.
 3. THE COST OF SIDE CURB SHALL BE INCLUDED IN PCC SIDEWALK 4".



FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ci:\pw\work\p\idot\steffenmk\d0187107\074475-shr-sidewalk-details.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 15.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/4/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SIDEWALK DETAILS
EAST WOOD STREET**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
712	128RS-4,148KRS-2	Macon	73	44
CONTRACT NO. 74475				
ILLINOIS FED. AID PROJECT				