

RESURFACING SCHEDULE	LENGTH	WIDTH OF RESURFACING	AREA	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	AGGREGATE WEDGE SHOULDER, TYPE B	TEMPORARY RAMP
STATION TO STATION	FOOT	FOOT	SQ YD	SQ YD	SQ YD	POUND	TON	TON	SQ YD
232+46.00 TO 232+76.00	30	30	100		100	45	8	2	17
232+76.00 TO 254+03.45	2127.45	30	7092	7092		3191	596	115	
254+03.45 (BK) = 254+26.76 (AH)		STATION EQUATION							
254+26.76 TO 262+42.30	816	30	2718	2718		1223	228	46	
262+42.30 TO 262+72.30	30	30	100		100	45	8	2	17
262+72.30 TO 267+68.40	496	BRIDGE OMISSION							
267+68.40 TO 267+98.40	30	30	100		100	45	8	2	17
267+98.40 TO 290+55.41	2257	30	7523	7523		3386	632	123	
290+55.41 (BK) = 291+04.94 (AH)		STATION EQUATION							
291+04.94 TO 294+32.00	327	30	1090	1090		491	92	19	
294+32.00 TO 294+62.00	30	30	100		100	45	8	2	17
PROJECT TOTALS				18424	400	8471	1581	310	68

PAVEMENT MARKING SCHEDULE	LENGTH	PAINT PAVEMENT MARKING - LINE 4"	RASIED REFLECTIVE PAVEMENT MARKER	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
STATION TO STATION	FOOT	FOOT	EACH	FOOT	SQ FT
232+46 TO 232+76	30.00	68	1	8	1
232+76 TO 254+03.45	2127.45	4787	27	424	70
254+03.45 (BK) = 254+26.76 (AH)	STATION EQUATION				
254+26.76 TO 262+42.30	815.54	1835	10	160	26
262+42.30 TO 262+72.30	30.00	68	1	8	1
262+72.30 TO 267+68.40	496.10	1116	BRIDGE		
267+68.40 TO 267+98.40	30.00	68	1	8	1
267+98.40 TO 290+55.41	2257.01	5006	28	448	74
290+55.41 (BK) = 291+04.94 (AH)	STATION EQUATION				
291+04.94 TO 294+32.00	327.06	736	4	64	11
294+32.00 TO 294+62.00	30.00	68	1	8	1
PROJECT TOTALS		13750	73	1128	115