

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				80% FED / 20% STATE CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	RURAL 0005	URBAN 0005	SN 061-0082 0014	SN 061-0066 0040
70400100	TEMPORARY CONCRETE BARRIER	FOOT	727	181		546	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	727	181		546	
70600340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	2		2	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1077	406	671		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	113484	109784	3700		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	257		257		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1596	1290	306		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 2.4"	FOOT	98	48	50		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	701	510	191		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	106	106			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	25	25			

SUMMARY OF QUANTITIES				80% FED / 20% STATE CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	RURAL 0005	URBAN 0005	SN 061-0082 0014	SN 061-0066 0040
78300100	PAVEMENT MARKING REMOVAL	SQ FT	471	471			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	697	506	191		
<del>89000100</del>	<del>TEMPORARY TRAFFIC SIGNAL INSTALLATION</del>	<del>EACH</del>	<del>2</del>	<del>1</del>		<del>1</del>	
X0323265	REMOVE EXISTING RIPRAP	SQ YD	66	66			
X4406040	PARTIAL DEPTH REMOVAL, TYPE I, 4"	SQ YD	171	98	73		
X4406240	PARTIAL DEPTH REMOVAL, TYPE II, 4"	SQ YD	113	95	18		
X4421000	PARTIAL DEPTH PATCHING	TON	14	10	4		
Ø 20076600	TRAINEES	HOURL	1000	500	500		
Ø 20076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURL	1000	500	500		
70600240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	2		2	

\* SPECIALTY ITEM

Ø 0042