

TRAFFIC CONTROL STAGING SCHEDULE

STATIONS	TEMPORARY RUMBLE STRIPS	TEMPORARY TRAFFIC SIGNAL INSTALLATION	WORK-ZONE PAVEMENT MARKING REMOVAL	REMOVE EXISTING PAVEMENT MARKING	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS (NON-REDIRECTIVE) TEST LEVEL 2	IMPACT ATTENUATORS, RELOCATE
	EACH	EACH	SQFT	SQFT	FOOT	FOOT	EACH	EACH
169+90	1							
174+90	1							
179+90	1							
203+24	1							
208+24	1							
213+24	1							
188+15							1	1
194+33							1	1
280+54.5							1	1
282+85.5							1	1
SN 061-0082		1						
SN 061-2456		1						
188+48 TO 193+94			364	364	546.0	546.0		
280+54.5 TO 282+35.5			107	107	181.0	181.0		
271+60	1							
266+60	1							
261+60	1							
291+36	1							
296+36	1							
301+36	1							
TOTAL:	12	2	471	471	727	727	4	4

JOINT OR CRACK ROUTING/FILLING SCHEDULE

STA.	TO	STA.	LENGTH	JOINT OR CRACK ROUTING PCC PAVEMENT AND SHOULDER	JOINT OR CRACK FILLING
			FOOT		
160+00	TO	203+63	4363	400	6479
TOTAL:				400	6479

SIDEWALK SCHEDULE

STATION	LT/RT	CURB AND GUTTER REMOVAL	COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.24	PCC SIDEWALK, 4"	SIDEWALK REMOVAL	DETECTABLE WARNINGS
		FT	FT	SQ FT	SQ FT	SQ FT
181+75	RT	7	7	42	42	10
181+75	LT	7	7	63	63	10
177+98	RT	7	7	55	55	10
177+98	LT	7	7	59	59	10
172+87	RT	9	9	50	50	10
172+87	LT	15	15	122	122	20
168+66	RT	13	13	137	84	20
168+66	LT	7	7	53	53	10
TOTALS		72	72	581	528	100