



CONCRETE REPLACEMENT

Note:

* Existing transverse bars extending from deck into removed area shall be cut allowing 2'-0" to extend into the removed area. In addition, these cut bars shall be cleaned, straighten, and incorporated into the new construction.

Existing reinforcement bars extending into removal area shall be cleaned, straightened and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Removal.

See sheet 6 of 10 for Section B-B.

DESIGNED - AYY	EXAMINED	DATE -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	JOINT REPLACEMENT (E. Abut.)		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CHECKED -	ENGINEER OF STRUCTURAL SERVICES	REVISOR		SN 082-0037		327	3BR-1-1-1	ST CLAIR	20	15
DRAWN - AYY	PASSED	REVISOR		SHEET NO. 5 OF 10 SHEETS		CONTRACT NO. 76C41				
CHECKED -	ENGINEER OF BRIDGES AND STRUCTURES	REVISOR		ILLINOIS FED. AID PROJECT						