

PAVEMENT MARKING SCHEDULE													
LOCATION			THERMOPLASTIC PAVEMENT MARKING AND TEMPORARY PAVEMENT MARKING							SHORT-TERM PAVEMENT MARKING (2 LIFTS) (WHITE)	SHORT-TERM PAVEMENT MARKING (2 LIFTS) (YELLOW)	WORKZONE PAVEMENT MARKING REMOVAL (SQ FT)	
			LINE, 4" SOLID (WHITE) FOOT	LINE, 4" DOUBLE SOLID FOOT	LINE, 4" SKIP-DASH (YELLOW) FOOT	LINE, 4" NO PASS EB (YELLOW) FOOT	LINE, 4" NO PASS WB (YELLOW) FOOT	LINE, 12" SOLID (WHITE) FOOT	LINE, 24" SOLID (WHITE) FOOT				LETTERS & SYMBOLS (WHITE) SQ FT
STA	TO	STA	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	
IL 140													
483+50		493+05	1950	3350				170	42	83	156	382	90
493+69		502+54	1649	3210				179	42	83	132	354	81
502+54		503+80	202	252							16	50	11
503+80		507+80	800		100						64	200	44
507+80		526+40	3670		465						294	372	111
526+40		536+60	2040		255	1020					163	510	112
536+60		546+05	1890	1890							151	378	88
546+05		552+50	1080	2350				122		31	86	258	57
553+15		557+06	485	1564				158			39	156	33
557+06		559+31	360	450							29	90	20
559+31		571+50	2438		305		1219				195	610	134
571+50		573+00	300		38						24	30	9
573+00		584+00	2200		275	1100					176	550	121
584+00		585+00	200	200							16	40	9
585+00		594+90	1980	1980	248		990				158	396	92
594+90		599+76	972		122						78	97	29
600+95		622+65	4340		543						347	434	130
626+55		636+45	1930		248						154	198	59
636+45		647+75	2260		283	1130					181	565	124
647+75		659+00	2200		281		1125				176	563	123
659+00		670+00	2200		275	1100					176	550	121
670+00		686+11	3092	3222							247	644	149
686+11		696+58	1978	1978							158	396	92
697+32		725+60	5456	5656							436	1131	261
725+60		733+25	1530		191		765				122	383	84
733+25		737+85	920	920							74	184	43
737+85		741+15	660		83	330					53	165	36
741+15		743+15	400		50						32	40	12
743+15		752+15	1650		225		900				132	450	97
752+15		785+90	6750		844						540	675	203
785+90		791+10	1040		130	520					83	260	57
791+10		792+10	200	200							16	40	9
792+10		797+10	1000		125		500				80	250	55
797+10		803+70	1320		165						106	132	40
803+70		809+65	1190		149	595					95	298	65
809+65		814+00	870		109						70	87	26
814+00		818+50	825		113		450				66	225	49
818+50		821+15	530	530							42	106	25
821+15		825+90	950		119	475					76	238	52
825+90		829+80	780		98						62	78	23
829+80		834+00	840		105		420				67	210	46
SUBTOTAL:			67127	27752	5939	6270	6769	629	84	198	5370	12774	3024
TOTAL:					113857			629	84	198	18144		3024

PAVEMENT PATCHING 17 INCH SCHEDULE						
LOCATION	LANE	LENGTH	LANE WIDTH	PAVEMENT PATCHING TYPE II	PAVEMENT PATCHING TYPE III	PAVEMENT PATCHING TYPE IV
	(EB/WB)	(FOOT)	(FOOT)	(SQ YD)	(SQ YD)	(SQ YD)
IL 140						
483 + 92	EB	8.0	12.5	11.1		
483 + 92	WB	8.0	12.5	11.1		
492 + 00	EB	100.0	12.0			133.3
504 + 10	EB	8.0	12.5	11.1		
512 + 00	EB	120.0	6.0			80.0
514 + 50	EB	60.0	6.0			40.0
530 + 00	EB	6.0	12.5	8.3		
530 + 00	WB	6.0	12.5	8.3		
531 + 00	EB	6.0	12.5	8.3		
531 + 00	WB	6.0	12.5	8.3		
546 + 00	WB	40.0	6.0			26.7
646 + 00	EB	60.0	6.0			40.0
655 + 00	EB	8.0	12.5	11.1		
660 + 00	EB	30.0	6.0		20.0	
666 + 00	EB	450.0	6.0			300.0
710 + 00	EB	60.0	6.0			40.0
712 + 50	EB	100.0	12.5			138.9
714 + 00	EB	120.0	6.0			80.0
737 + 20	EB	500.0	6.0			333.3
753 + 00	EB	8.0	12.5	11.1		
756 + 00	EB	50.0	6.0			33.3
764 + 00	EB	760.0	6.0			506.7
772 + 00	EB	550.0	6.0			366.7
779 + 00	EB	50.0	6.0			33.3
786 + 50	EB	250.0	6.0			166.7
791 + 50	EB	15.0	12.5		20.8	
791 + 50	WB	15.0	12.5		20.8	
793 + 00	EB	6.0	12.5	8.3		
793 + 00	WB	6.0	12.5	8.3		
805 + 00	EB	60.0	6.0			40.0
829 + 00	EB	10.0	12.5	13.9		
829 + 00	WE	10.0	12.5	13.9		
SUBTOTAL:				133.3	61.7	2358.9
ANTICIPATED FAILURES (15%):				20.0	9.3	353.8
TOTAL:				153	71	2713

SHOULDER RUMBLE STRIPS			
LOCATION			SHOULDER RUMBLE STRIPS 8"
STA	TO	STA	(FOOT)
IL 140 - RIGHT			
484+00	TO	492+05	805
495+35	TO	498+35	300
500+00	TO	502+50	250
546+05	TO	552+25	620
553+50	TO	557+06	356
672+30	TO	686+01	1371
686+79	TO	696+48	969
697+42	TO	707+25	983
IL 140 - LEFT			
484+00	TO	491+40	740
494+65	TO	499+30	465
499+80	TO	500+85	105
501+35	TO	502+50	115
546+05	TO	551+15	510
553+85	TO	557+06	321
672+30	TO	673+85	155
672+30	TO	686+01	1371
686+79	TO	696+48	969
697+42	TO	707+25	983
TOTAL:			11388

RAISED PAVEMENT MARKERS						
LOCATION			RAISED REFLECTOR PAVEMENT MARKER ONE-WAY AMBER	RAISED REFLECTOR PAVEMENT MARKER ONE-WAY CRYSTAL	RAISED REFLECTOR PAVEMENT MARKER TWO-WAY AMBER	RAISED REFLECTOR PAVEMENT MARKER REMOVAL
STA	TO	STA	(EACH)	(EACH)	(EACH)	(EACH)
IL 140						
483+50	TO	493+05	38	5	12	55
493+69	TO	503+34	38	4	14	56
503+34	TO	545+25	53			53
545+25	TO	552+50	26	4	14	44
553+15	TO	557+86	26		6	32
557+86	TO	599+76			52	52
600+95	TO	622+65			27	27
626+55	TO	686+11			74	74
686+11	TO	696+58			12	12
697+32	TO	834+00			170	170
SUBTOTAL:			181	13	381	575
TOTAL:				575		575

FRAMES & GRATES TO BE ADJUSTED		
LOCATION	RT/LT	(EACH)
STA. 685+95	RT/LT	2
STA. 697+48	LT	1
TOTAL:		3

STONE RIPRAP CLASS A2		
LOCATION	FILTER FABRIC	STONE RIPRAP CLASS A2
IL 140	(SQ YD)	(SQ YD)
SN 060-2491 (RIGHT)	375	375
SN 060-2491 (LEFT)	325	325
SN 060-2492 (RIGHT)	425	425
SN 060-2492 (LEFT)	425	425
TOTAL:		1550