

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0005 80% FED 20% STATE	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1588	1588	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1737	1737	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	42	42	
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2	
54010505	PRECAST CONCRETE BOX CULVERTS 5' X 5'	FOOT	60	60	
54213873	STEEL END SECTIONS 18"	EACH	2	2	
54260311	TRAVERSABLE PIPE GRATE	FOOT	75	75	
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	53	53	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3	
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	11388	11388	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0005 80% FED 20% STATE	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	35	35	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	18144	18144	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	198	198	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	113857	113857	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	629	629	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	84	84	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3024	3024	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	450	450	