PAVEMENT MARKING SCHEDULE

LOCATION STATION	TO	STATION	SHORT TERM PAVEMENT MARKING (FOOT)	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS (SQ FT)	TEMPORARY PAVEMENT MARKING LINE 4" (FOOT)	TEMPORARY PAVEMENT MARKING LINE 8" (FOOT)	TEMPORARY PAVEMENT MARKING LINE 12" (FOOT)	TEMPORARY PAVEMENT MARKING LINE 24" (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	WHITE THERMOPLASTIC PAVEMENT MARKING LETTERS & SYMBOLS (SQ FT)	WHITE THERMOPLASTIC PAVEMENT MARKING LINE 4" (FOOT)	YELLOW THERMOPLASTIC PAVEMENT MARKING LINE 4" (FOOT)	WHITE THERMOPLASTIC PAVEMENT MARKING LINE 8" (FOOT)	WHITE THERMOPLASTIC PAVEMENT MARKING LINE 12" (FOOT)	YELLOW THERMOPLASTIC PAVEMENT MARKING LINE 12" (FOOT)	WHITE THERMOPLASTIC PAVEMENT MARKING LINE 24" (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	PAVEMENT MARKING REMOVAL (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)
BASE BID																			
IL RTE 154																			
148+62	TO	169+59	650	63	8,439		248		217	63	2,539	5,900			248		60	200	33
PRAIRIE ROAD																			
8+80.5	TO	10+41.1				135	88	36					135	88		36			
SUBTOTAL			**650**	**63**	**8,439**	**135**	**336**	**36**	**217**	**63**	**2,539**	**5,900**	**135**	**88**	**248**	**36**	**60**	**200**	**33**
TOTAL BASE BID			**650**	**63**	**8,439**	**135**	**336**	**36**	**217**	**63**	**8,439**		**135**	**336**		**36**	**60**	**200**	**33**

PREPARED BY:JGG - CHECKED BY: TJL

EROSION CONTROL SCHEDULE

LOCATION STATION	TO	STATION	PERIMETER EROSION BARRIER (FOOT)	STONE RIPRAP, CLASS A4 (SQ YD)	FILTER FABRIC (SQ YD)
BASE BID					
IL RTE 154					
152+62	TO	165+59	2,472	11	11
TOTAL BASE BID			2,472	11	11

PREPARED BY:JGG CHECKED BY:TJL

PAVEMENT SCHEDULE

LOCATION STATION	TO	STATION	HMA BASE COURSE WIDENING 9" (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	TEMPORARY RAMP (SQ YD)	POLYMERIZED HMA SURFACE COURSE, MIX "D", N70 (TON)	STRIP REFFLECTIVE CRACK CONTROL TREATMENT (FOOT)	HMA SHOULDERS, 6" (SQ YD)	SHOULDER RUMBLE STRIPS, 8 INCH (FOOT)
BASE BID										
IL RTE 154										
152+62	TO	165+59	1,100	1.53	7	48	687	647	984	2,310
PRAIRIE ROAD										
8+80.5	TO	10+41.1		0.21	1	54	96		127	
TOTAL BASE BID			**1,100**	**1.7**	**8**	**102**	**783**	**647**	**1,111**	**2,310**

PREPARED BY:JGG - CHECKED BY: TJL

PAVEMENT PATCHING SCHEDULE

LOCATION *			LANE	LENGTH (FT)	LANE WIDTH (FT)	PAVEMENT PATCHING TYPE I, 12 INCH (SQ YD)	PAVEMENT PATCHING TYPE II, 12 INCH (SQ YD)	PAVEMENT PATCHING TYPE III, 12 INCH (SQ YD)
	+		EB	3.0	13.0	4.3		
	+		EB	4.0	13.0		5.8	
	+		EB	6.0	13.0		8.7	
	+		EB	12.0	13.0			17.3
	+		WB	3.0	13.0	4.3		
	+		WB	4.0	13.0		5.8	
	+		WB	6.0	13.0		8.7	
	+		WB	12.0	13.0			17.3
SUBTOTAL:						8.7	28.9	34.7
ANTICIPATED FAILURES (15%):						1.3	4.3	5.2
TOTAL:						10	33	40

* PATCHING LOCATIONS TO BE DETERMINED BY THE ENGINEER

EROSION CONTROL SCHEDULE

LOCATION STATION	OFFSET	RT/LT	TEMPORARY DITCH CHECKS (FOOT)	INLET AND PIPE PROTECTION (EACH)
BASE BID				
IL RTE 154				
153+98.3	23.4	LT	15	
154+78.1	31.1	RT	20	
155+36.0	27.6	LT	15	
156+72.4	30.8	LT	10	
156+99.5	32.4	RT	15	
158+08.0	33.9	LT	10	
158+08.1	35.2	RT	10	
158+60.9	32.4	LT	10	
158+64.7	30.8	LT		1
159+00.2	42.6	RT	10	
162+96.0	32.1	LT	10	
163+83.4	31.1	RT	10	
164+23.1	33	LT	10	
165+00.0	38.4	LT	10	
165+59.0	29.6	RT	10	
PRAIRIE ROAD				
TOTAL BASE BID			**165**	**1**

PREPARED BY:JGG CHECKED BY:TJL

SEEDING SCHEDULE

LOCATION STATION	TO	STATION	SEEDING, CLASS 2A (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH, METHOD 2 (ACRE)
BASE BID							
IL RTE 154							
152+62	TO	165+59	0.73	70	70	70	0.73
PRAIRIE ROAD							
8+80.5	TO	10+41.1	0.02	2	2	2	0.02
TOTAL BASE BID			0.75	72	72	72	0.75

PREPARED BY:JGG - CHECKED BY: TJL

SIGN SCHEDULE

LOCATION STATION	OFFSET	SIGN DESCRIPTION	RELOCATE SIGN PANEL ASSEMBLY TYPE A (EACH)	TELESCOPING STEEL SIGN SUPPORT (FOOT)
BASE BID				
IL ROUTE 154				
156+66	RT	PRAIRIE MILE MARKER	1	15
157+00	LT	ADOPT-A-HIGHWAY KEEP ILLINOIS CLEAN	1	16.5
158+34	LT	ILLINOIS 154	1	14
159+37	LT	S. PRAIRIE RD. N. PRAIRIE RD.	1	14
160+74	RT	ILLINOIS 154	1	14
162+00	LT	PRAIRIE	1	13.5
PRAIRIE ROAD				
9+18		STOP CROSS TRAFFIC DOES NOT STOP	1	14.5
9+49		STOP	1	13.5
TOTAL BASE BID			8	115

PREPARED BY:JGG - CHECKED BY: TJL

PAVEMENT REMOVAL SCHEDULE

LOCATION STATION	TO	STATION	HMA SURFACE REMOVAL, BUTT JOINT (SQ YD)	HMA SURFACE REMOVAL, 3/4" (SQ YD)
BASE BID				
IL RTE 154				
152+62	TO	165+59	288	3,458
PRAIRIE ROAD				
8+80.5	TO	10+41.1	161	579
TOTAL BASE BID			449	4,037

PREPARED BY:JGG CHECKED BY:TJL

EARTHWORK SCHEDULE

LOCATION STATION	TO	STATION	RT/LT	1 EARTH EXCAVATION (CU YD)	2 NO PAY ITEM [1] X [1 - 0.25] MATERIALS TO BE USED IN EMBANKMENT (ADJUSTED FOR SHRINKAGE) (CU YD)	3 NO PAY ITEM EMBANKMENT (CU YD)	4 NO PAY ITEM EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
BASE BID							
ILRTE 154							
152+62	TO	159+00		217	163	142	21
159+00	TO	165+59		365	274	164	110
TOTAL BASE BID				582	437	306	131

PREPARED BY:MSJ CHECKED BY:JGG

DRIVER = i:\Bentley8i\prnt\plotdr-v\ILDOT\ILDOT.pdf.bwpltcfg
FILE NAME = X:\CIVIL\2011\11004-18\CAD\files to IDOT\D876G70-sht-schedule.dgn

Foth
Foth Infrastructure & Environment, LLC

USER NAME = JGG	DESIGNED - JGG	REVISED -
PRINTER =	DRAWN - MSJ	REVISED -
PLOT SCALE = 2.00 ' / in.	CHECKED - MJB	REVISED -
PLOT DATE = 3/20/2014	DATE - 3-18-14	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NTS | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
329	125-I	RANDOLPH	20	5

CONTRACT NO. 76G70

ILLINOIS FED. AID PROJECT