

SUMMARY OF QUANTITIES

90% FED / 10% STATE

SUMMARY OF QUANTITIES			TOTAL	CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	QUANTITIES	0004
20200100	EARTH EXCAVATION	CU YD	582	582
25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72	72
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72	72
25000800	POTASSIUM FERTILIZER NUTRIENT	POUND	72	72
25100115	MULCH, METHOD 2	ACRE	0.75	0.75
28000305	TEMPORARY DITCH CHECKS	FOOT	165	165
28000400	PERMETER EROSION BARRIER	FOOT	2,472	2,472
28000500	INLET AND PIPE PROTECTION	EACH	1	1
28100107	STONE RIPRAP, CLASS A4	SQ YD	11	11
28200200	FILTER FABRIC	SQ YD	11	11
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	1,100	1,100
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.7	1.7
40600300	AGGREGATE (PRIME COAT)	TON	8	8
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	448	448
40600990	TEMPORARY RAMP	SQ YD	102	102
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	783	783
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	4,037	4,037
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	10	10
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	33	33
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	40	40
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	647	647
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1,111	1,111

90% FED / 10% STATE

SUMMARY OF QUANTITIES			TOTAL	CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	QUANTITIES	0004
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	2,310	2,310
67100100	MOBILIZATION	LSUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100480	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	650	650
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SC FT	63	63
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8,439	8,439
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	135	135
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	336	336
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	36	36
70201000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,387	3,387
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	8	8
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	115	115
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SC FT	63	63
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8,439	8,439
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	135	135
* 78000800	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	336	336
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	36	36
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	60	60
78300100	PAVEMENT MARKING REMOVAL	SQ FT	200	200
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	33	33

* SPECIALTY ITEM

ORDER: I:\Bentley\Bentley\Projects\11007\11007.dwg, 11007.dwg, 11007.dwg
 FILE NAME: I:\Bentley\Bentley\Projects\11007\11007.dwg, 11007.dwg, 11007.dwg
 PLOT DATE: 3/28/2014



USER NAME: jdc	DESIGNED: JGC	REVISED: -
PRINTER: -	DRAWN: MSJ	REVISED: -
PLOT SCALE: 2.00 / 1.00	CHECKED: MJB	REVISED: -
PLOT DATE: 3/28/2014	DATE: 3-18-14	REVISED: -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE. 329	SECTION 125-1	COUNTY RANDOLPH	TOTAL SHEETS 20	SHEET NO. 3
CONTRACT NO. 76G70			ILLINOIS FED. AID PROJECT	