

INDEX OF SHEETS

1. COVER SHEET
2. GENERAL NOTES, INDEX OF SHEETS & HIGHWAY STANDARDS
3. SUMMARY OF QUANTITIES
- 4.-6. TYPICAL SECTIONS
7. SCHEDULES
8. LOCATION MAP
9. CRACK & JOINT SEALING DETAIL

STANDARDS

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
701101-04	OFF-RD OPERATIONS, MULTILANE, 15'(4.5m) TO 24'(600mm) FROM EDGE OF PAVEMENT
701106-02	OFF-RD OPERATIONS, MULTILANE, MORE THAN 15'(4.5m) AWAY
701400-07	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-08	LANE CLOSURE FREEWAY/EXPRESSWAY
701411-08	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS ≥ 45MPH
701426-06	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS ≥ 45MPH
701428	TRAFFIC CONTROL SETUP AND REMOVAL FREEWAY/EXPRESSWAY
701901-03	TRAFFIC CONTROL DEVICES

GENERAL NOTES

1. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. (1-800-892-0123 OR 811) OR FOR NON-MEMBERS THE UTILITY COMPANY DIRECTLY.
2. UTILITY INTERFERENCES ARE NOT ANTICIPATED ON THIS CONTRACT. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE HIS CONSTRUCTION ACTIVITIES WITH THE VARIOUS UTILITY OWNERS. ALL POTENTIAL CONFLICTS SHALL BE INVESTIGATED AND REMEDIAL ACTION TAKEN PRIOR TO INTERRUPTION OF THE CONTRACTOR'S PROGRESS. NO ADDITIONAL COST SHALL BE ADDED TO THE CONTRACT RESULTING FROM UTILITY CONFLICTS.
3. FLAGGERS SHALL BE PRESENT DURING ALL CLOSURE HOURS INCLUDING LUNCH HOUR AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.
4. ANY RAISED REFLECTIVE PAVEMENT MARKERS ENCOUNTERED SHALL BE LEFT IN PLACE. ROUTING SHALL BE GAPPED WHERE RAISED REFLECTIVE PAVEMENT MARKERS ARE ENCOUNTERED SO AS TO LEAVE THEM FUNCTIONAL.
5. RESIDENT ENGINEER SHALL DETERMINE EXACT LOCATION WHERE CRACKS ARE TO BE ROUTED AND FILLED.
6. ESTIMATED APPLICATION RATES : 0.33 LB/FT
7. CARE SHALL BE TAKEN TO AVOID ALL PAVEMENT MARKING CENTERLINES. ANY PAVEMENT MARKING DISTURBED FOR ANY REASON BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT NO COST TO THE DEPARTMENT OF TRANSPORTATION.
8. AN AMOUNT OF 53930 FOOT THERMOPLASTIC PAVEMENT MARKING - LINE 6" HAS BEEN ADDED TO THE PLANS TO ACCOUNT FOR CRACKS ROUTED AND SEALED ON I-70'S EDGELINES.
9. AN AMOUNT OF 2160 FOOT SHORT TERM PAVEMENT MARKING FOR DIAGONALS ALONG I-70 HAS BEEN ADDED TO THE PLANS AND 713 SQ FT WORK ZONE PAVEMENT MARKING REMOVAL.
9. ALL STRUCTURES ARE OMITTED FROM THE CONTRACT.
10. IT IS THE INTENT OF THIS PROJECT TO ROUTE AND SEAL THE CENTERLINES. ROUTING AND SEALING WILL ALSO BE DONE AT THE TRANSVERSE JOINTS AT ALL BRIDGE AND LARGE MULTI-LANE CONCRETE PATCHES. ADDITIONAL TRANSVERSE JOINTS ARE TO BE ROUTED AND SEALED ON I-70 AT INTERVALS APPROXIMATELY 50' OR WHERE INDICATED BY THE ENGINEER.
11. THE RESIDENT ENGINEER SHALL VERIFY THE EXISTENCE OF IN PAVEMENT DETECTOR LOOPS. THE APPROXIMATE LOCATIONS ARE AS FOLLOWS:  
 I-55/70 - 38°40'03"N/90°02'56"W - MILE 8.856  
 I-55 - 38°48'26"N/89°53'32"W - MILE 24.057  
 THESE PIEZOMETER/DETECTOR LOOPS SHALL BE AVOIDED DURING THE OPERATION OF ROUTING AND SEALING. IF THESE LOOPS ARE DISTURBED BY THE CONTRACTOR, THEY SHALL BE REPAIRED/REPLACED AT THE CONTRACTOR'S EXPENSE AND AS DIRECTED BY THE ENGINEER.
12. THE ILLINOIS DEPARTMENT OF TRANSPORTATION STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB-CONTRACTORS TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERALLY FUNDED HIGHWAY CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORKFORCE AND TRAINEE GOALS. THIS PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION-RELATED SKILLS, E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSEWORK (CARPENTRY, CONCRETE FLATWORK, BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION, TO PREPARE THEM FOR A CAREER IN THE HIGHWAY CONSTRUCTION TRADES. GRADUATES ARE WELL-TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEVEL CONSTRUCTION WORKERS. PLEASE CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCTP COORDINATOR AT 618/874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE AND TRAINEE GOALS.

FILE NAME =	USER NAME = wadmora_jb	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>				F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pvc\work\pvidot\wadmora_jb\0366798\dt\76g88-ahs-plan.dgn	DRAWN -	REVISED -	55/70						60-16,7,9,9,10,1,60-(1,2)-3	MADISON	9	2	
PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT						
PLOT DATE = 3/28/2014	DATE -	REVISED -	CONTRACT NO. 76G88										