

CRACK SEALING SCHEDULE 01								
LOCATION				NUMBER OF LONGITUDINAL LINES	TRANSVERSE JOINT LENGTH	CRACK ROUTING (PAVEMENT)	CRACK FILLING	COMMENT
MI. STA.	TO	MI. STA.	DIRECTION		FOOT	FOOT	POUND	
I-55/70								
8.122	TO	8.179	SB	2		602	198.6	3 LANES/2 CENTERLINES
8.179	TO	8.232	SB		72	72	23.8	BRIDGE OMISSION SN 060-0011
8.232	TO	8.680	SB	2		4731	1561.2	3 LANES/2 CENTERLINES
8.680	TO	9.260	SB	3		9187	3031.8	4 LANES/3 CENTERLINES
9.260	TO	10.515	SB	2		13253	4373.4	3 LANES/2 CENTERLINES
10.515	TO	10.838	SB	1		1705	562.8	2 LANES/1 CENTERLINE
10.838	TO	10.892	SB		48	48	15.8	BRIDGE OMISSION SN 060-0013
10.892	TO	11.394	SB	1		2651	874.7	2 LANES/1 CENTERLINE
11.394	TO	11.448	SB		48	48	15.8	BRIDGE OMISSION SN 060-0015
11.448	TO	12.975	SB	1		8063	2660.6	2 LANES/1 CENTERLINE
12.975	TO	13.014	SB		48	48	15.8	BRIDGE OMISSION SN 060-0017
13.014	TO	16.079	SB	1		16183	5340.5	2 LANES/1 CENTERLINE
16.079	TO	16.107	SB		48	48	15.8	BRIDGE OMISSION SN 060-0019
16.107	TO	17.820	SB	1		9045	2984.7	2 LANES/1 CENTERLINE
17.820	TO	17.895	SB		48	48	15.8	CONCRETE PATCH OMISSION @ IL 162
17.895	TO	18.055	SB	1		845	278.8	2 LANES/1 CENTERLINE
18.055	TO	18.537	SB	2		5090	1679.7	3 LANES/2 CENTERLINES
8.375	TO	8.490	NB	2		1214	400.8	3 LANES/2 CENTERLINES
8.490	TO	8.414	NB		72	72	23.8	BRIDGE OMISSION SN 060-0010
8.414	TO	8.827	NB	2		4361	1439.2	3 LANES/2 CENTERLINES
8.827	TO	9.268	NB	3		6985	2305.2	4 LANES/3 CENTERLINES
9.268	TO	11.069	NB	2		19019	6276.1	3 LANES/2 CENTERLINES
11.069	TO	11.130	NB		72	72	23.8	BRIDGE OMISSION SN 060-0012
11.130	TO	11.379	NB	2		2629	867.7	3 LANES/2 CENTERLINES
11.379	TO	11.675	NB	1		1563	515.8	2 LANES/1 CENTERLINE
11.675	TO	11.722	NB		48	48	15.8	BRIDGE OMISSION SN 060-0014
11.722	TO	13.213	NB	1		7872	2597.9	2 LANES/1 CENTERLINE
13.213	TO	13.247	NB		48	48	15.8	BRIDGE OMISSION SN 060-0016
13.247	TO	16.304	NB	1		16141	5326.5	2 LANES/1 CENTERLINE
16.304	TO	16.332	NB		48	48	15.8	BRIDGE OMISSION SN 060-0018
16.332	TO	18.073	NB	1		9192	3033.5	2 LANES/1 CENTERLINE
18.073	TO	18.148	NB		48	48	15.8	CONCRETE PATCH OMISSION @ IL 162
18.148	TO	18.400	NB	1		1331	439.1	2 LANES/1 CENTERLINE
18.400	TO	18.930	NB	2		5597	1846.9	3 LANES/2 CENTERLINES
SUB-TOTAL THIS SCHEDULE						147907	48809	

CRACK SEALING SCHEDULE 02								
LOCATION				NUMBER OF LONGITUDINAL LINES	TRANSVERSE JOINT LENGTH	CRACK ROUTING (PAVEMENT)	CRACK FILLING	COMMENT
MI. STA.	TO	MI. STA.	DIRECTION		FOOT	FOOT	POUND	
I-55								
18.537	TO	22.330	SB	1		20027	6608.9	2 LANES/1 CENTERLINE
22.330	TO	22.445	SB		48	48	15.8	CONCRETE PATCH OMISSION @ IL 143
22.445	TO	24.567	SB	1		11204	3697.4	2 LANES/1 CENTERLINE
24.567	TO	24.611	SB		48	48	15.8	BRIDGE OMISSION SN 060-0002
24.611	TO	29.602	SB	1		26352	8696.3	2 LANES/1 CENTERLINE
29.602	TO	29.771	SB		48	48	15.8	CONCRETE PATCH OMISSION @ IL 140
29.771	TO	31.051	SB	1		6758	2230.3	2 LANES/1 CENTERLINE
18.930	TO	22.571	NB	1		19224	6344.1	2 LANES/1 CENTERLINE
22.571	TO	22.686	NB		48	48	15.8	CONCRETE PATCH OMISSION @ IL 143
22.686	TO	24.872	NB	1		11542	3808.9	2 LANES/1 CENTERLINE
24.872	TO	24.865	NB		48	48	15.8	BRIDGE OMISSION SN 060-0004
24.865	TO	29.821	NB	1		26168	8635.3	2 LANES/1 CENTERLINE
29.821	TO	29.990	NB		48	48	15.8	CONCRETE PATCH OMISSION @ IL 140
29.990	TO	31.218	NB	1		6484	2139.7	2 LANES/1 CENTERLINE
I-70								
14.042	TO	14.497	WB	3	2306	14126	4661.6	2 LANES/1 CENTERLINE-2 EDGELINES
14.497	TO	14.617	WB		96	96	31.7	BRIDGE OMISSION SN 060-0022
14.617	TO	16.147	WB	3	7755	47501	15675.3	2 LANES/1 CENTERLINE-2 EDGELINES
16.147	TO	16.177	WB		96	96	31.7	BRIDGE OMISSION SN 060-0024
16.177	TO	16.796	WB	3	3138	19218	6341.8	2 LANES/1 CENTERLINE-2 EDGELINES
14.257	TO	16.147	EB	3	9580	58678	19363.6	2 LANES/1 CENTERLINE-2 EDGELINES
16.147	TO	16.177	EB		96	96	31.7	BRIDGE OMISSION SN 060-0023
16.177	TO	16.790	EB	3	3107	19031	6280.4	2 LANES/1 CENTERLINE-2 EDGELINES
SUB-TOTAL THIS SCHEDULE						286890	94674	
SUB-TOTAL SCHEDULE 01 & 02						434797	143483	
25% ALLOWANCE FOR FAILURES						108699	35871	
GRAND TOTAL						543497	179354	