

PAVEMENT PATCHING SCHEDULE

STATION	LOCATION			DIMENSIONS		PARTIAL DEPTH REMOVAL, TYPE II, 3"	PARTIAL DEPTH REMOVAL, TYPE III, 3"	PARTIAL DEPTH REMOVAL, TYPE IV, 3"	PARTIAL DEPTH PATCHING	CLASS D PATCHES, TYPE II, 12"	CLASS D PATCHES, TYPE III, 12"	CLASS D PATCHES, TYPE IV, 12"
	TO	STATION	DIRECTION	LENGTH	WIDTH	SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD	SQ YD
3.732			NB	6	12					8		
3.732			SB	6	12					8		
4.334			SB	6	12					8		
4.392			SB	8	12					11		
4.452			SB	6	12					8		
4.469			SB	6	12					8		
4.471			SB	6	12					8		
4.482			SB	6	12					8		
4.486			SB	6	12					8		
4.490			SB	6	12					8		
4.502			SB	6	12					8		
7.436			NB	12	12						16	
7.436			SB	12	12						16	
10.510	*		NB	12	12	16			2.7			
10.510	*		SB	12	12	16			2.7			
10.635			NB	12	12	16			2.7			
10.635			SB	12	12	16			2.7			
10.699			NB	6	12					8		
10.699			SB	6	12					8		
10.720			NB	10	12					14		
10.720			SB	10	12					14		
10.868			NB	6	12	8			1.3			
10.868			SB	6	12	8			1.3			
10.879			NB	6	12	8			1.3			
10.879			SB	6	12	8			1.3			
10.895			NB	6	12	8			1.3			
10.895			SB	6	12	8			1.3			
10.926			NB	6	12					8		
10.926			SB	6	12					8		
10.945			NB	6	12	8			1.3			
10.945			SB	6	12	8			1.3			
11.186			SB	6	12	8			1.3			
11.570			NB	6	12	8			1.3			
11.690			NB	8	12	11			1.8			
11.690			SB	8	12	11			1.8			
13.676			NB	60	12							80
13.676			SB	15	12						20	
14.054			SB	8	12					11		
14.083			SB	60	12		80		13.4			
14.143			SB	30	12	40			6.7			
14.150			SB	30	12							40
14.156			NB	40	12							54
14.176			SB	12	12						16	
16.118	16.237		SB	629	12			839	141.0			
16.363	16.513		SB	793	12			1058	177.7			
16.435			SB	25	12							34
16.531			SB	50	12							67
17.130	17.191		SB	323	12			431	72.4			
19.375			SB	60	12		80		13.4			
21.952			SB	50	12		67		11.3			
SUBTOTALS						206	227	2328	463.8	162	68	275
15% ALLOWANCE**						31	34	349	69.6	24	10	41
TOTALS						237	261	2677	533.4	186	78	316

*SKEW PATCH TO ALIGN WITH UNDERLYING CULVERT.

** AN ADDITIONAL 10% HAS BEEN ADDED TO THE FINAL PATCHING QUANTITY TO ALLOW FOR UNFORSEEN DETERIORATION DISCOVERED DURING THE PATCHING PROCESS.

FILE NAME =	USER NAME = wedmore.jb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p\dot\wedmore.jb\d0366809\d876g99-sht-plen.dgn	DRAWN -	REVISED -	314/670			(30,66)I, (108,109,110-2)I-1	MADISON	5	5	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 76C89							
PLOT DATE = 3/28/2014	DATE -	REVISED -	SCALE:			SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.