SIDE ROAD & ENTRANCE SCHEDULE

LOCATION	TYPE	WIDTH		MAILBOX LOCATION	BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	INCIDENTAL HMA SURFACING (TON)	AGGREGATE SURFACE COURSE TYPE B FIELD ENTRANCE (TON)	EXISTING SURFACE TYPE	COMMENTS
		A	B							
STA. 261+47 RT	FE	30	25	NO				0.4	EARTH	
STA. 261+80 LT	PE	23	18	NO				0.3	AGG	
STA. 263+21 RT	PE	38	34	NO				0.5	AGG	
STA. 264+36 LT	CE	31	25	NO	0.004	0.02	1.2		CONC/HMA	
STA. 266+32 RT	PE	42	34	266+09 RT				0.6	AGG	
STA. 266+13.80	SR	58	51	NO	0.008	0.04	2.5		HMA	900 N. - METCALF RD.
STA. 267+20 LT	FE	42	37	NO				0.6	AGG	
STA. 269+84 RT	PE	43	39	NO				0.6	AGG	
STA. 271+18 RT	PE	39	32	272+38 RT				0.5	AGG	
STA. 272+63 LT	PE	39	33	272+58 RT	0.003	0.02	0.9		HMA	
STA. 276+41 RT	PE	45	38	276+69 RT				0.6	AGG	
STA. 284+00 RT	FE	30		NO				0.5	EARTH	
STA. 287+34.65 RT	SR	100	85	NO	0.011	0.06	4.0		HMA	860 N.
STA. 309+62 LT	FE	33	25	NO				0.6	AGG	
STA. 344+88 LT	FE	16		NO				0.3	EARTH	
SUB-TOTAL								5.5		
TOTAL SHEET 1								9.4		
TOTAL					0.026	0.14	8.6	14.9		
ROUNDING					0.03 •		9	15 •		

• - SEE MAINLINE RESURFACING SCHEDULE FOR FINAL QUANTITY

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
		CHECKED -	REVISED -
	PLOT SCALE =	DRAWN -	REVISED -
	PLOT DATE =	CHECKED -	REVISED -

Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL.
62703 Phone: (217)544-8033 IL. Design Firm
No. 184-001907

QUANTITY SCHEDULES

SHEET NO. 2 OF 5 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(55,56)RS-3	GREENE	15	10
		CONTRACT NO. 76H12		
	ILLINOIS	FED. AID PROJECT		