

PAVEMENT PATCHING, TYPE II, 8 INCH				
LOCATION		LENGTH	WIDTH	
STATION	RT/LT	FT	FT	SQ. YD.
341+00.00	LT	5.00	12.00	6.67
341+00.00	RT	5.00	12.00	6.67
339+00.00	LT	5.00	12.00	6.67
339+00.00	RT	5.00	12.00	6.67
338+00.00	LT	5.00	12.00	6.67
338+00.00	RT	5.00	12.00	6.67
337+00.00	LT	5.00	12.00	6.67
337+00.00	RT	5.00	12.00	6.67
336+00.00	LT	5.00	12.00	6.67
336+00.00	RT	5.00	12.00	6.67
335+00.00	LT	5.00	12.00	6.67
335+00.00	RT	5.00	12.00	6.67
334+00.00	LT	5.00	12.00	6.67
334+00.00	RT	5.00	12.00	6.67
333+00.00	LT	6.00	12.00	8.00
333+00.00	RT	6.00	12.00	8.00
332+00.00	LT	5.00	12.00	6.67
332+00.00	RT	5.00	12.00	6.67
331+00.00	LT	6.00	12.00	8.00
331+00.00	RT	6.00	12.00	8.00
329+00.00	LT	5.00	12.00	6.67
329+00.00	RT	5.00	12.00	6.67
328+00.00	LT	6.00	12.00	8.00
328+00.00	RT	6.00	12.00	8.00
327+00.00	LT	5.00	12.00	6.67
327+00.00	RT	5.00	12.00	6.67
326+00.00	LT	5.00	12.00	6.67
326+00.00	RT	5.00	12.00	6.67
325+00.00	LT	6.00	12.00	8.00
325+00.00	RT	6.00	12.00	8.00
324+00.00	LT	6.00	12.00	8.00
324+00.00	RT	6.00	12.00	8.00
323+00.00	LT	6.00	12.00	8.00
323+00.00	RT	6.00	12.00	8.00
322+00.00	LT	6.00	12.00	8.00
322+00.00	RT	6.00	12.00	8.00
321+00.00	LT	6.00	12.00	8.00
321+00.00	RT	6.00	12.00	8.00
320+00.00	LT	6.00	12.00	8.00
320+00.00	RT	6.00	12.00	8.00
310+00.00	LT	6.00	12.00	8.00
310+00.00	RT	6.00	12.00	8.00
309+00.00	LT	5.00	12.00	6.67
309+00.00	RT	5.00	12.00	6.67
308+00.00	LT	6.00	12.00	8.00
308+00.00	RT	6.00	12.00	8.00
SUB-TOTAL (1)				336

PAVEMENT PATCHING, TYPE II, 8 INCH				
LOCATION		LENGTH	WIDTH	
STATION	RT/LT	FT	FT	SQ. YD.
307+00.00	LT	5.00	12.00	6.67
307+00.00	RT	5.00	12.00	6.67
306+50.00	LT	5.00	12.00	6.67
306+50.00	RT	5.00	12.00	6.67
305+00.00	LT	6.00	12.00	8.00
305+00.00	RT	6.00	12.00	8.00
303+00.00	LT	6.00	12.00	8.00
303+00.00	RT	6.00	12.00	8.00
302+00.00	LT	6.00	12.00	8.00
302+00.00	RT	6.00	12.00	8.00
300+00.00	LT	6.00	12.00	8.00
300+00.00	RT	6.00	12.00	8.00
299+00.00	LT	6.00	12.00	8.00
299+00.00	RT	6.00	12.00	8.00
298+00.00	LT	5.00	12.00	6.67
298+00.00	RT	5.00	12.00	6.67
297+00.00	LT	6.00	12.00	8.00
297+00.00	RT	6.00	12.00	8.00
295+00.00	LT	5.00	12.00	6.67
295+00.00	RT	5.00	12.00	6.67
294+00.00	LT	6.00	12.00	8.00
294+00.00	RT	6.00	12.00	8.00
293+00.00	LT	6.00	12.00	8.00
293+00.00	RT	6.00	12.00	8.00
292+00.00	LT	5.00	12.00	6.67
292+00.00	RT	5.00	12.00	6.67
291+00.00	LT	5.00	12.00	6.67
291+00.00	RT	5.00	12.00	6.67
289+00.00	LT	6.00	12.00	8.00
289+00.00	RT	6.00	12.00	8.00
287+00.00	LT	6.00	12.00	8.00
287+00.00	RT	6.00	12.00	8.00
286+00.00	LT	6.00	12.00	8.00
285+00.00	LT	6.00	12.00	8.00
285+00.00	RT	6.00	12.00	8.00
284+00.00	LT	6.00	12.00	8.00
284+00.00	RT	6.00	12.00	8.00
283+00.00	LT	6.00	12.00	8.00
283+00.00	RT	6.00	12.00	8.00
282+00.00	LT	6.00	12.00	8.00
282+00.00	RT	6.00	12.00	8.00
280+00.00	LT	6.00	12.00	8.00
280+00.00	RT	6.00	12.00	8.00
276+40.00	LT	6.00	12.00	8.00
276+40.00	RT	6.00	12.00	8.00
SUB-TOTAL				344
SUB-TOTAL (1)				336
ANTICIPATED FAILURES (20%)				136
TOTAL				816

FILE NAME =

USER NAME =
 PLOT SCALE =
 PLOT DATE =

DESIGNED -
 CHECKED -
 DRAWN -
 CHECKED -

REVISED -
 REVISED -
 REVISED -
 REVISED -



Allen Henderson & Associates, Inc.
 Civil and Structural Engineers Springfield, IL
 62703 Phone: (217)544-8033 IL Design Firm
 No. 184-001907

QUANTITY SCHEDULES

SHEET NO. 5 OF 5 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(55,56)RS-3	GREENE	15	13
				CONTRACT NO. 76H12
ILLINOIS FED. AID PROJECT				