

PAVEMENT MARKING SCHEDULE

STATION TO STATION			THERMOPLASTIC PAVEMENT MARKING							SHORT TERM PAVEMENT MARKING*	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS	RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL
			LINE 4"				LINE 6"	LINE 24"	LETTERS & SYMBOLS				
			SKIP DASH WHITE	SKIP DASH YELLOW	SOLID YELLOW	SOLID WHITE	SOLID WHITE	SOLID WHITE					
			FOOT	FOOT	FOOT	FOOT	FOOT	FOOT					
US 51 (WASHINGTON ST.)													
977+00.00	TO	980+00.00	128	14	418	109		34	36.4	232.9	405	22	22
980+00.00	TO	983+71.00	178	64.3	459.6	449		49	72.8	442.1	702	30	30
983+71.00	TO	990+00.00	314.2	314.2	1256.6				62.4	685.6	919	44	44
990+00.00	TO	998+00.00	400.0	400.0	1600.0				93.6	872.7	1185	60	60
998+00.00	TO	1004+00.00	300.0	300.0	1200.0				62.4	654.5	881	44	44
1004+00.00	TO	1006+40.00	125.0	125.0	500.0			44.0	153.6	272.7	583	16	16
1006+40.00	TO	1006+47.00	RR OMISSION										
1006+47.00	TO	1009+00.00	123.0	123.0	492.0			44.0	153.6	268.4	577	16	16
1009+00.00	TO	1013+00.00	200.0	20.0	1135.1	100	138		67.6	491.2	785	27	27
1013+00.00	TO	1017+87.00	203.1		823.6	300.00	138		72.8	415.9	723	36	36
1017+87.00	TO	1023+00.00	785.0		838.0	319.00		81	81.5	428.2	1034	40	40
US 51 (POPLAR ST.)													
20+24.00	TO	16+20.00			756.4	100.0		28.0	62.4	233.7	482	15	15
16+20.00	TO	2+15.00	OMISSION										
2+15.00	TO	1+12.00			206.0			20.0			109	2	2
US 51 (HICKORY ST.)													
99+15.00	TO	100+21.00			148.0			11		40.4	85	2	2
TOTAL			2756	1361	9833	1377	276	311	919	5038	8468	354	354
			15327										

•ONE APPLICATION EACH FOR HMA SURFACE REMOVAL, BINDER, AND SURFACE