

				CONSTR. CODE
				100% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY
				0005
				RURAL
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	61631	61631
40600370	LONGITUDINAL JOINT SEALANT	FOOT	20945	20945
40600405	MATERIAL TRANSFER DEVICE	TON	8920	8920
40600900	HOT-MIX ASPHALT BINDER COURSE (HAND METHOD), N50	TON	42	42
40600990	TEMPORARY RAMP	SQ YD	326	326
40602965	HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N50	TON	5489	5489
40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	8920	8920
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	123	123
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1351	1351
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	23595	23595
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	55992	55992
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	202	202
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	303	303
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	2020	2020

*SPECIALTY ITEM

MODEL: Summary of Quantities 1 [Sheet]
FILE NAME: X:\BM3-1733 D2 Various Phase I\BM3-1733C_WO3 64U24 IL 2617 Drawings\03 Sheets\ID2-64U24-sh1-SOQ.dgn

 BLOOM COMPANIES, LLC Infrastructure Association and Integrity 100 N. Wacker Drive, Suite 1800 • Chicago, IL 60606 Phone: (312) 876-9300 Fax: (312) 876-9800	USER NAME = ssaste	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -						316	101PP&RS	STEPHENSON	35	4
	PLOT SCALE = 0.16666633' / in.	CHECKED -	REVISED -		CONTRACT NO. 64U24								
	PLOT DATE = 12/11/2024	DATE	REVISED -		SCALE: Full Size 1 = 1	SHEET	OF	SHEETS	STA.	TO STA.			

ENTRANCE SCHEDULE

				40600290	40800050	44000155
Location	Existing Surface Condition	SQ FT	SQ YD	Bituminous Materials (Tack Coat)	INC HMA Surface	HMA Surface Removal, 1 1/2"
				POUND	TON 1 1/2"	SQ YD

STA		RT/LT		REMARKS							
673	+	92	LT	PE	HMA	292	33	15	3		33
677	+	40	LT	PE	HMA	503	56	26	5		56
681	+	33	LT	PE	HMA	202	23	11	2		23
682	+	10	LT	PE	HMA	268	30	14	3		30
684	+	33	RT	PE	HMA	318	36	17	4		36
684	+	84	LT	FE	AGG		0	0	0		0
692	+	74	RT	PE	HMA	253	29	14	3		29
698	+	23	RT	PE	HMA	458	51	23	5		51
704	+	67	RT	PE	HMA	354	40	18	4		40
706	+	85	LT	PE	HMA	987	110	50	10		110
714	+	17	RT	PE	HMA	406	46	21	4		46
716	+	49	RT	FE	AGG		0	0	0		0
728	+	95	LT	PE	HMA	792	89	41	8		89
739	+	51	RT	PE	AGG		0	0	0		0
748	+	62	LT	PE	HMA	422	47	22	4		47
754	+	68	RT	FE	AGG		0	0	0		0
757	+	42	RT	PE	HMA	581	65	30	6		65
763	+	93	RT	FE	AGG		0	0	0		0
777	+	64	RT	FE	AGG		0	0	0		0
779	+	57	RT	PE	HMA	376	42	19	4		42
783	+	77	LT	PE	HMA	612	69	32	6		69
790	+	60	LT	PE	HMA	610	68	31	6		68
796	+	65	RT	PE	AGG		0	0	0		0
804	+	53	RT	PE	HMA	608	68	31	6		68
806	+	45	RT	PE	HMA	1023	114	52	10		114
809	+	50	RT	PE	HMA	1137	127	58	11		127
813	+	53	RT	PE	HMA	650	73	33	7		73
816	+	20	RT	PE	CONC		0	0	0		0
832	+	67	LT	FE	AGG		0	0	0		0
832	+	67	RT	FE	AGG		0	0	0		0
849	+	60	LT	FE	AGG		0	0	0		0
849	+	65	RT	PE	HMA	633	71	32	6		71
858	+	09	RT	PE	HMA	573	64	29	6		64
863	+	37	LT	FE	AGG		0	0	0		0
TOTAL								619	123		1351

MODEL: Entrance schedule (Sheet)
FILE NAME: X:\BIM3-1733 D2 Various Phase H\BIM3-1733C_W03 64U24 IL 2617_Drawings\03 Sheets\02-64U24-sht-Schedule of Quantities.dgn