



BILL OF MATERIALS - MAIN PARK ROAD

ITEM	UNIT	TOTAL
EARTH EXCAVATION	CU YD	74
TRENCH BACKFILL	CU YD	2.6
GRADING AND SHAPING DITCHES	FOOT	2,619
AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	71
AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	139
AGGREGATE SURFACE COURSE, TYPE A	TON	6.2
LEVELING BINDER (MACHINE METHOD), N50	TON	121.4
HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	216
HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N50	TON	26.5
HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,303.5
CLASS D PATCHES, TYPE IV, 6 INCH	SO YD	460
STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	116
PAVEMENT REMOVAL	SO YD	63
AGGREGATE WEDGE SHOULDER, TYPE B	TON	123.5
PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	41
END SECTIONS 12"	EACH	2
SIGN PANEL - TYPE 1	SO FT	36
REMOVE SIGN PANEL - TYPE 1	SO FT	10
WOOD SIGN SUPPORT	FOOT	117
PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,535
PAINT PAVEMENT MARKING - LINE 24"	FOOT	22
REMOVE EXISTING GATE	EACH	2
TUBULAR STEEL GATE	EACH	2
FOLD DOWN BOLLARDS	EACH	2
BOLLARD REMOVAL	EACH	2
EARTH EXCAVATION (SPECIAL)	CU YD	60
PIPE CULVERTS TO BE CLEANED 12"	FOOT	108
PIPE CULVERTS TO BE CLEANED 15"	FOOT	349
PIPE CULVERTS TO BE CLEANED 18"	FOOT	57
PIPE CULVERTS TO BE CLEANED 24"	FOOT	90
PIPE CULVERTS TO BE CLEANED 36"	FOOT	102
PIPE CULVERTS TO BE CLEANED 84"	FOOT	71
REMOVE SIGN COMPLETE	EACH	5
BITUMINOUS MATERIALS (PRIME COAT)	POUND	6,430

* PATCHING QUANTITIES ARE ESTIMATED AND SHALL ONLY BE USED AT THE DISCRETION OF THE ENGINEER.

FILE NAME : L:\1007\106610\W0.1510-a\106610.Sheets\46251-sht-MainPark-0175-1toPlan01.dgn	USER NAME : Brad Downen	DESIGNED - MJD	REVISED -
Default	Plot SCALE = 48.0000' / in.	DRAWN - RAH	REVISED -
	Plot DATE = 4/6/2013	CHECKED - BJO	REVISED -
		DATE - 3/29/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SITE PLAN - MAIN PARK ROAD
KANKAKEE RIVER STATE PARK**

SCALE: 1" = 20' SHEET 1 OF 6 SHEETS STA. 50+00 TO STA. 55+00

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PARK ROADS		140	55
* WILL & KANKAKEE			CONTRACT NO. 46251	
ILLINOIS FED. AID PROJECT				