



BILL OF MATERIALS - NORTH LOOP

ITEM	UNIT	TOTAL
LEVELING BINDER (MACHINE METHOD), N50	TON	46.5
HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	232
HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,140.2
HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	105
AGGREGATE WEDGE SHOULDER, TYPE B	TON	98.0
SIGN PANEL - TYPE 1	SO FT	10
REMOVE SIGN PANEL - TYPE 1	SO FT	3
WOOD SIGN SUPPORT	FOOT	15
PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,742
PAINT PAVEMENT MARKING - LINE 24"	FOOT	20
REMOVE EXISTING GATE	EACH	1
REMOVE EXISTING PARKING BLOCKS	EACH	91
PRECAST CONCRETE PARKING BLOCK	EACH	91
TUBULAR STEEL GATE	EACH	1
ENTRANCE SIGN	L SUM	1
REMOVE SIGN (SPECIAL)	EACH	1
AGGREGATE SHOULDERS (SPECIAL)	TON	2.5
PIPE CULVERTS TO BE CLEANED 12"	FOOT	113
PIPE CULVERTS TO BE CLEANED 15"	FOOT	34
PIPE CULVERTS TO BE CLEANED 24"	FOOT	72
PIPE CULVERTS TO BE CLEANED 36"	FOOT	99
REMOVE SIGN COMPLETE	EACH	1
BITUMINOUS MATERIALS (PRIME COAT)	POUND	4,773

FILE NAME :	USER NAME : Brad Downen	DESIGNED - MJO	REVISED -
L:\DOT\1186618\10_15\10-ev\10400_Sheets\0346251-sh1-NorthLoop-801\Alignment.dgn	DRAWN - RAH	CHECKED - BJO	REVISED -
Default	PLOT SCALE = 100.0000 1 / in.	DATE - 3/29/2013	REVISED -
	PLOT DATE = 4/6/2013		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ALIGNMENT AND BILL OF MATERIALS - NORTH LOOP
KANKAKEE RIVER STATE PARK**

SCALE: 1" = 50' SHEET 1 OF 5 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PARK ROADS		140	73
* WILL & KANKAKEE			CONTRACT NO. 46251	
ILLINOIS FED. AID PROJECT				