



BILL OF MATERIALS - DAVIS CREEK CAMPGROUND

ITEM	UNIT	TOTAL
EARTH EXCAVATION	CU YD	342
FURNISHED EXCAVATION	CU YD	10
TRENCH BACKFILL	CU YD	6.5
TOPSOIL FURNISH AND PLACE, 4"	SO YD	198
GRADING AND SHAPING DITCHES	FOOT	140
AGGREGATE BASE COURSE, TYPE A	TON	498.2
AGGREGATE BASE COURSE, TYPE A 2"	SO YD	5,682
AGGREGATE BASE COURSE, TYPE A 12"	SO YD	736
AGGREGATE SURFACE COURSE, TYPE A	TON	25.0
HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N50	TON	825.5
HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	625.1
PAVEMENT REMOVAL	SO YD	80
AGGREGATE WEDGE SHOULDER, TYPE B	TON	152.2
PIPE CULVERT REMOVAL	FOOT	40
PIPE CULVERTS, CLASS D, TYPE I 15"	FOOT	55
END SECTIONS 15"	EACH	2
SIGN PANEL - TYPE 1	SO FT	20
REMOVE SIGN PANEL - TYPE 1	SO FT	3
WOOD SIGN SUPPORT	FOOT	92
PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,280
PAINT PAVEMENT MARKING - LINE 24"	FOOT	15
UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	2,140
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	6,450
LIGHT POLE, WOOD, 30 FOOT, CLASS 5	EACH	1
REMOVE EXISTING GATE	EACH	1
REMOVE EXISTING PARKING BLOCKS	EACH	45
PRECAST CONCRETE PARKING BLOCK	EACH	47
TUBULAR STEEL GATE	EACH	1
SCARIFY EXISTING SURFACE	SO YD	5,682
AGGREGATE SHOULDERS (SPECIAL)	TON	4.3
PIPE CULVERTS TO BE CLEANED 24"	FOOT	55
SIGN PANEL - TYPE 1 (SPECIAL)	SO FT	34
REMOVE SIGN COMPLETE	EACH	1
LUMINAIRE (SPECIAL)	EACH	1
BITUMINOUS MATERIALS (PRIME COAT)	POUND	15,786

FILE NAME : L:\IDOT\1186610\15\DWG\CADD_Sheets\46251-sht-DavisCreek-00\Alignment.dgn	USER NAME : Brad Downen	DESIGNED - MJJ	REVISED -
		DRAWN - RAH	REVISED -
		CHECKED - BJD	REVISED -
		DATE - 3/29/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ALIGNMENT AND BILL OF MATERIALS - DAVIS CREEK CAMPGROUND
KANKAKEE RIVER STATE PARK

SCALE: 1" = 50' SHEET 1 OF 7 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PARK ROADS		140	85
* WILL & KANKAKEE			CONTRACT NO. 46251	
ILLINOIS FED. AID PROJECT				