

SUMMARY OF QUANTITIES			CONSTRUCTION CODE 0005			
			100% STATE TOTAL QUANTITY	NORTH SITE	SOUTH SITE	EAST SITE
CODE NO.	ITEM DESCRIPTION	UNIT				
28000400	PERIMETER EROSION BARRIER	FOOT	1,575	879	696	
28000500	INLET AND PIPE PROTECTION	EACH	14	6	4	4
28100105	STONE RIPRAP, CLASS A3	SO YD	39	25		14
28200200	FILTER FABRIC	SO YD	306	25		281
35101400	AGGREGATE BASE COURSE, TYPE B	TON	2,109.3	91.3	47.3	1,970.7
35200300	PROCESSING SOIL-CEMENT BASE COURSE 8"	SO YD	6,662			6,662
35200500	CEMENT	100 WT	3,757			3,757
35800100	PREPARATION OF BASE	SO YD	6,662			6,662
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	478.2	478.2		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,038	714	102	5,222
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	133.1	133.1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	136	136		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,776.2	20.5	10.7	1,745.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2,065.1	627.1	95.9	1,342.1