NORTH DAY USE ENTRANCE DRIVE

LIMITS OF CONSTRUCTION

℄ NORTH DAY USE ENTRANCE DRIVE

LIMITS OF CONSTRUCTION

EARTH EXCAVATION- 30 CU. YD.
PROPOSED HMA SURFACE COURSE, MIX "C", N50- 2"
PROPOSED HMA BINDER COURSE, IL- 19.0, N50- 2"
PROPOSED AGGREGATE BASE COURSE, TYPE B- 8"

408 +38.39 409 +40.18 410+00

90°00'00" 90°00'00"

11'± 11'± 1'

1' PROPOSED AGGREGATE WEDGE SHOULDER

LIMITS OF CONSTRUCTION

LIMITS OF CONSTRUCTION

GRAVEL

GRAVEL

FROM ℄ OF NORTH DAY USE ENTRANCE DRIVE 50'

EARTH EXCAVATION- 30 CU. YD.
PROPOSED HMA SURFACE COURSE, MIX "C", N50- 2"
PROPOSED HMA BINDER COURSE, IL- 19.0, N50- 2"
PROPOSED AGGREGATE BASE COURSE, TYPE B- 8"

15' (TYP.) 15' (TYP.)

GRAVEL

EQUESTRIAN PARKING LOT

25' (TYP.) 25' (TYP.)

GRAVEL

MAINTAIN EXISTING EDGE OF PAVEMENT

PROPOSED AGGREGATE SURFACE COURSE, TYPE B
(VARIABLE THICKNESS 2¼ TO 7½ INCHES)

LEGEND

PROPOSED
EXISTING

N

10' 0 10' 20'
SCALE: 1" = 10'

FILE NAME =	USER NAME = Brian Bond	DESIGNED - BMB	REVISED -
L:\IDOT\1180618\K0_13\Draw\CADD_Sheets\D746255_Grading Staking Plan-North Equestrian.dgn		DRAWN - RAH	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED - JMM	REVISED -
Defaults	PLOT DATE = 3/29/2013	DATE - 3/29/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

NORTH DAY USE EQUESTRIAN LOT – GRADING & STAKING PLAN
NEWTON LAKE STATE FISH AND WILDLIFE AREA

SCALE: AS NOTED | SHEET OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	PARKS ROADS	JASPER	66	24
		CONTRACT NO. 46255		
	ILLINOIS FED. AID PROJECT			