

URBAN
90% FED.
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE							
				ROADWAY	LANDSCAPING	BRIDGE	BRIDGE	BRIDGE	MINOR STRUCTURES	SAFETY	
				0004 S.N.	0001 URBAN	0011 S.N. 016-1322	0011 S.N. 016-1323	0011 S.N. 016-2573	0040 S.N. 016-2014	0021 URBAN	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	727	727							
42100340	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	212	212							
42100615	PAVEMENT REINFORCEMENT	SQ YD	939	939							
44000100	PAVEMENT REMOVAL	SQ YD	4196	4196							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	110	110							
44001980	CONCRETE BARRIER REMOVAL	FOOT	1766	1766							
44003100	MEDIAN REMOVAL	SQ FT	319	319							
44004250	PAVED SHOULDER REMOVAL	SQ YD	4141	4141							
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	300	300							
44213200	SAW CUTS	FOOT	1343	1343							
44213202	TIE BARS 1"	EACH	340	340							
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	500	500							
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	837	837							
48300505	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/4"	SQ YD	3679	3679							
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SQ YD	1448	1448							
50101700	REMOVAL OF EXISTING SUPERSTRUCTURES NO. 1	EACH	1					1			
50102400	CONCRETE REMOVAL	CU YD	173.5					173.5			

17

FILE NAME : I:\7888 - 194 at Ohio St - 03\ADDON\AQO SHEETS\DIR\63-500.dgn

* - DENOTES SPECIALTY ITEM
 ☐ - DENOTES 100% CITY OF CHICAGO
 △ - DENOTES NON-PARTICIPATING ITEM

Rev.



USER NAME : rgo11	DESIGNED -	REVISED -
PLOT SCALE : 2,000' / 1"	DRAWN -	REVISED -
PLOT DATE : 3/25/2013	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-90/94 AT OHIO STREET
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	0303-474B-R	COOK	368	5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60F63	