

URBAN
90% FED.
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE						
				ROADWAY	LANDSCAPING	BRIDGE	BRIDGE	BRIDGE	MINOR STRUCTURES	SAFETY
				0004 S.N.	0001 URBAN	0011 S.N. 016-1322	0011 S.N. 016-1323	0011 S.N. 016-2573	0040 S.N. 016-Z014	0021 URBAN
50200100	STRUCTURE EXCAVATION	CU YD	832.1					321.4	510.7	
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	1323.6			298.2	1025.4			
50300225	CONCRETE STRUCTURES	CU YD	889.3			261.4	108.0	375.0	144.9	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1181.5			591.3	397.6	192.6		
50300260	BRIDGE DECK GROOVING	SQ YD	1921			1345	576			
50300285	FORM LINER TEXTURED SURFACE	SQ FT	1447					1447		
50300300	PROTECTIVE COAT	SQ YD	3910			2475	1435			
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	1371					1371		
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	11480					11480		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			0.81	0.19			
50500505	STUD SHEAR CONNECTORS	EACH	13928			9903	2853		1172	
50800105	REINFORCEMENT BARS	POUND	65240			50870	14370			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	460676			230740	118650	89120	22166	
50800515	BAR SPLICERS	EACH	2138			1379	651	108		
50800530	MECHANICAL SPLICERS	EACH	1464			1050	276	138		
50901730	BRIDGE FENCE RAILING	FOOT	126					126		
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	396					396		

17

FILE NAME = H:\2003 - 194 of Ohio Street\ROAD\ADD SHEETS\016RF-EJ-S00.dgn

* - DENOTES SPECIALTY ITEM
 [Symbol] - DENOTES 100% CITY OF CHICAGO
 [Symbol] - DENOTES NON-PARTICIPATING ITEM



USER NAME = rjg011	DESIGNED -	REVISED -
PLOT SCALE = 2,0000 1/4" = 1'	DRAWN -	REVISED -
PLOT DATE = 3/25/2013	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-90/94 AT OHIO STREET
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	0303-474B-R	COOK	368	7
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60F63	