URBAN
90% FED-
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE ROADWAY 0004 S.N.	~~LANDSCAPING~~ ~~0021~~ ~~URBAN~~	BRIDGE 0011 S.N. 016-1322	BRIDGE 0011 S.N. 016-1323	BRIDGE 0011 S.N. 016-2573	MINOR STRUCTURES 0040 S.N. 016-Z014	SAFETY 0021 URBAN
51202305	DRIVING PILES	FOOT	396					396		
51203200	TEST PILE METAL SHELLS	EACH	1					1		
51500100	NAME PLATES	EACH	3			1	1	1		
51602000	PERMANENT CASING	FOOT	1864			1109	755			
51603000	DRILLED SHAFT IN SOIL	CU YD	345			218.4	126.2			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	205			104	101			
52100520	ANCHOR BOLTS, 1"	EACH	168			112	56			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1						
5421A012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	130	130						
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	243	243						
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	99	99						
550A0930	STORM SEWERS, CLASS A, TYPE 4 10"	FOOT	56	56						
550A0940	STORM SEWERS, CLASS A, TYPE 4 12"	FOOT	410	410						
550A0960	STORM SEWERS, CLASS A, TYPE 4 15"	FOOT	75	75						
55100400	STORM SEWER REMOVAL 10"	FOOT	24	24						
55100500	STORM SEWER REMOVAL 12"	FOOT	651	651						
55100700	STORM SEWER REMOVAL 15"	FOOT	94	94						

17

• - DENOTES SPECIALTY ITEM
▭ - DENOTES 100% CITY OF CHICAGO
△ - DENOTES NON-PARTICIPATING ITEM

FILE NAME = 1:\2008 - I94 at Ohio Street\C420\C420 SHEETS\0160F63-SQ01.dgn

COLLINS ENGINEERS INC

USER NAME = rgoll	DESIGNED -	REVISED -
PLOT SCALE = 2.0000 ' / in.	DRAWN -	REVISED -
PLOT DATE = 3/25/2013	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-90/94 AT OHIO STREET
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	0303-474HB-R	COOK	368	8
		CONTRACT NO. 60F63		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT