

URBAN  
90% FED.  
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE							
				ROADWAY	LANDSCAPING	BRIDGE	BRIDGE	BRIDGE	MINOR STRUCTURES	SAFETY	
				0004 S.N.	<del>0001</del> URBAN	0011 S.N. 016-1322	0011 S.N. 016-1323	0011 S.N. 016-2573	0040 S.N. 016-Z014	0021 URBAN	
55100900	STORM SEWER REMOVAL 18"	FOOT	100	100							
55101100	STORM SEWER REMOVAL 21"	FOOT	18	18							
56200900	WATER SERVICE LINE 2 1/2"	FOOT	120	120	<del>120</del>						
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	1770					1770			
58700300	CONCRETE SEALER	SQ FT	8347			2020	1030	2279		3018	
59000200	EPOXY CRACK INJECTION	FOOT	10					10			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	427					310		117	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	13.3					13.3			
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	3	3							
60100945	PIPE DRAINS 12"	FOOT	42	42							
60107600	PIPE UNDERDRAINS 4"	FOOT	2496	2496							
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	84	84							
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1							
60200205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
60200305	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1							
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	6	6							
60201005	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 10 FRAME AND GRATE	EACH	1	1							

17

• - DENOTES SPECIALTY ITEM  
 100 - DENOTES 100% CITY OF CHICAGO  
 △ - DENOTES NON-PARTICIPATING ITEM

FILE NAME: I-90-94 AT OHIO STREET - 194 AT OHIO STREET - 194 AT OHIO STREET - SHEET 016 OF 63 - 500.dgn



USER NAME: rgoj	DESIGNED: -	REVISED: -
PL01 SCALE: 2,000' = 1"	DRAWN: -	REVISED: -
PL07 DATE: 3/25/2013	CHECKED: -	REVISED: -
	DATE: -	REVISED: -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

I-90/94 AT OHIO STREET  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.I.T. RTE. 90/94	SECTION 0303-474HB-R	COUNTY COOK	TOTAL SHEETS 368	SHEET NO. 9
CONTRACT NO. 60F63				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				