URBAN
90% FED.
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE ROADWAY 0004 S.N.	~~LANDSCAPING~~ ~~0031~~ ~~URBAN~~	BRIDGE 0011 S.N. 016-1322	BRIDGE 0011 S.N. 016-1323	BRIDGE 0011 S.N. 016-2573	MINOR STRUCTURES 0040 S.N. 016-Z014	SAFETY 0021 URBAN
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	8	8						
60202215	CATCH BASINS, TYPE A, 4'-DIAMETER, WITH MEDIAN INLET (604101)	EACH	2	2						
60203805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1						
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1						
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1						
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3						
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	3	3						
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4	4						
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	4	4						
60250200	CATCH BASINS TO BE ADJUSTED	EACH	10	10						
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1						
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	2	2						
60253800	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 8 GRATE	EACH	2	2						
△ 60255410	CATCH BASINS TO BE CLEANED	EACH	1	1						
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3						
60500040	REMOVING MANHOLES	EACH	9	9						
60500050	REMOVING CATCH BASINS	EACH	9	9						

1/X

• - DENOTES SPECIALTY ITEM
▭ - DENOTES 100% CITY OF CHICAGO
△ - DENOTES NON-PARTICIPATING ITEM

FILE NAME = IN7800 - 194 at Ohio Street\CADD\CADD SHEETS\016SF63-SD0.dgn

COLLINS ENGINEERS INC

USER NAME = rgall	DESIGNED -	REVISED -
PLOT SCALE = 2.0000 ' / in.	DRAWN -	REVISED -
PLOT DATE = 3/25/2013	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-90/94 AT OHIO STREET
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	0303-474HB-R	COOK	368	10

CONTRACT NO. 60F63

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT